



AFCAP Project Phase 4

Back Analysis of Previous Low Volume Rural Roads in Mozambique

DRAFT PROJECT INCEPTION REPORT

Project Reference AFCAP/MOZ/001/G

Report No. CPR 1410

Transport Research Laboratory



DRAFT PROJECT REPORT

Analysis of Performance of Previous Low Volume Rural Roads in Mozambique

Inception Report

Prepared for: Project Record: AFCAP/MOZ/001/G

Inception Report

Client: AFCAP

**Mozambican National Roads Administration
(ANE)**

Copyright Transport Research Laboratory September 2012

This Draft Report has been prepared for AFCAP and ANE for the sole purpose of Project Report Review.

The views expressed are those of the author(s) and not necessarily those of AFCAP or ANE.

| | Name | Date Approved |
|--------------------------|----------------|----------------------|
| Project Manager | Kenneth Mukura | |
| Technical Referee | John Rolt | |

Contents

| | | |
|--------------|---|------------------|
| 1 | Introduction | 5 |
| 2 | Objectives of the Rural Roads Investment Programme (RRIP)..... | 5 |
| 3 | Report Objectives..... | 6 |
| 4 | Project Organisation | 6 |
| 4.1 | Project Team | 6 |
| 5 | Project Scope | 8 |
| 5.1 | Preliminary Activities..... | 9 |
| 5.2 | Field Investigations..... | 9 |
| 5.3 | Materials Testing..... | 10 |
| 5.4 | Analysis and Documentation | 10 |
| 5.5 | Reporting..... | 10 |
| 5.6 | Transfer of Knowledge | 11 |
| 6 | Progress..... | 11 |
| 6.1 | Selection of Candidate Roads..... | 11 |
| 6.2 | Data Collection..... | 11 |
| 6.2.1 | <i>As-Built Data</i> | <i>12</i> |
| 6.2.2 | <i>Maintenance Records.....</i> | <i>12</i> |
| 6.2.3 | <i>Deflection Data.....</i> | <i>12</i> |
| 6.2.4 | <i>Laboratory capacities to carry out surveys and testing.....</i> | <i>13</i> |
| 6.2.5 | <i>Traffic Data</i> | <i>14</i> |
| 6.2.6 | <i>Rainfall Data</i> | <i>14</i> |
| 6.3 | Selection of Sub Sections | 16 |
| 7 | Details of the Road Sections | 16 |
| 7.1 | General | 16 |
| 7.2 | Classification of Road Condition | 16 |
| 7.3 | Maputo..... | 17 |
| 7.3.1 | <i>Marracuene – Ferroviario Road (Unclassified).....</i> | <i>17</i> |
| 7.3.2 | <i>Boane – Limbobos – Goba Road (R400).....</i> | <i>20</i> |
| 7.4 | Inhambane..... | 23 |
| 7.4.1 | <i>Pambarra – Rio Save Road (N1).....</i> | <i>23</i> |
| 7.5 | Zambezia | 26 |
| 7.5.1 | <i>Rio Zambezi – Nicoadala Road (N1)</i> | <i>26</i> |
| 7.5.2 | <i>Quelimane – Namacurra Road (N10)</i> | <i>28</i> |
| 7.6 | Nampula..... | 30 |
| 7.6.1 | <i>Nametil-Angoche Road (N104).....</i> | <i>30</i> |
| 7.7 | Cabo Delgado..... | 32 |
| 7.7.1 | <i>Oasse-Mocimboa da Praia Road (N380).....</i> | <i>32</i> |
| 7.8 | Niassa | 35 |
| 7.8.1 | <i>Maniamba-Metangula Road (N361).....</i> | <i>35</i> |
| 7.8.2 | <i>Lichinga-Mandimba Road (N13).....</i> | <i>39</i> |
| 8 | Recommendations | 42 |

| | | |
|-----------|--|-----------|
| 9 | Programme for Detailed Investigations | 44 |
| 9.1 | Field Investigations..... | 44 |
| 9.2 | Materials Testing..... | 44 |
| 9.3 | Analysis and Documentation | 45 |
| 10 | References..... | 50 |
| | Appendix A - Assessment of Laboratory Capacity..... | 51 |
| | Appendix B – Cyclones Data..... | 59 |
| | Appendix C – Rainfall Data..... | 61 |
| | Appendix D –Map of Study Roads..... | 73 |

Tables

| | | |
|------------|--|----|
| Table 4-1 | Local team structure | 6 |
| Table 6-1 | Key data for candidate roads..... | 15 |
| Table 7-1 | Road condition criteria..... | 16 |
| Table 7-2 | Properties of study sections..... | 18 |
| Table 7-3 | Properties of study sections | 21 |
| Table 7-4 | Properties of study sections..... | 24 |
| Table 7-5 | Properties of study sections..... | 27 |
| Table 7-6 | Properties of study sections..... | 29 |
| Table 7-7 | Properties of study sections..... | 31 |
| Table 7-8 | Properties of study sections..... | 33 |
| Table 7-9 | Properties of study sections..... | 37 |
| Table 7-10 | Characteristics of study sections | 40 |
| Table 8-1 | Summary of road characteristics | 42 |
| Table 8-2 | Recommended roads and study sections..... | 43 |
| Table 9-1 | Materials required to assess performance | 48 |

Figures

| | | |
|------------|--|----|
| Figure 7-1 | Typical Sections of the Marracuenne – Ferroviario Road | 19 |
| Figure 7-2 | Typical Sections of the Boane – Limbombos – Goba Road | 22 |
| Figure 7-3 | Typical Sections of the Pambarra – Rio Save Road | 26 |
| Figure 7-4 | Typical Sections of the Rio Zambezi – Nicoadala Road | 28 |
| Figure 7-5 | Typical sections of the Quelimane – Namacurra Road..... | 30 |
| Figure 7-6 | Typical sections of the Nametil-Angoche road..... | 32 |
| Figure 7-7 | Typical sections of the Oasse-Mocimboa da Praia road | 35 |
| Figure 7-8 | Typical Sections of the Maniamba-Metangula road | 39 |
| Figure 7-9 | Typical sections of the Lichinga-Mandimba road | 41 |
| Figure 9-1 | Activity Schedule..... | 47 |

1 Introduction

The Mozambican National Roads Administration (ANE) has embarked on a Regional Roads Investment Programme (RRIP). The programme is being supported by the Swedish International Development Agency (ASDI), which is providing the funding for construction works, including site supervision, and by the UK's Department for International Development (DFID) through its African Community Access Programme (AFCAP)¹, which is providing technical assistance for research, application of innovative solutions, development of guidelines, communication, and mainstreaming.

TRL has been commissioned by Crown Agents to carry out Phase 4 of the AFCAP programme in Mozambique to undertake a back analysis of previously constructed low volume roads (LVRs) and monitor their historic and current performance.

2 Objectives of the Rural Roads Investment Programme (RRIP)

The objective of ANE's RRIP is to bring important unpaved low-volume roads to an improved standard to maximise interconnectivity and all-weather passability on the network, and reduce longer term maintenance costs. The concept of the programme is based on the "targeted interventions" (spot improvement) approach, and the intention is to apply a range of road construction technologies suitable for the varying conditions found in the country. This includes areas in the coastal zone where materials suitable for the construction of low traffic roads by traditional means cannot be found within a reasonable haul distance. Stand-alone "pilot" projects are being carried out in all ten provinces of Mozambique.

The overall programme is being managed by the ANE Directorate of Maintenance (DIMAN) in Maputo. The individual projects are being administered by the provincial delegations of ANE (DPANE), with technical support from DIMAN. The design of the works and site supervision is being carried out by DPANE and their provincial consultants.

The current programme involves both demonstrations of relatively well-understood methods in Mozambique which are covered by regional or international design standards, but which may require local modifications, and innovative solutions that are best described as research. There are many sections of road that have been built in Mozambique in the past where low cost techniques have been applied. For example, the use of emulsion stabilised sand for road bases has been the subject of experimentation in Mozambique over several years. However, there has been no systematic monitoring of these sections of road and therefore no scientific evaluation of their performance in relation to the designs, materials, traffic level, environmental conditions or quality of construction. The latter, for example, plays a significant role in the deterioration of roads and is always a factor that must be evaluated, especially when new methods are being introduced that contractors are not familiar with. Therefore there is a risk of the contractors not complying with appropriate standards and specifications.

Furthermore, appropriate maintenance regimes are required for roads built using non-conventional materials and sealed with low cost surfacing. In order to be effective, the maintenance regime should be linked to the designs, materials, the environment and the traffic. The Africa Community Access Programme (AFCAP) has agreed to assist ANE with the back-analysis of the performance of a number of sections that were built in the last two decades prior to the current programme. This will involve detailed research on their construction, pavement design as built, materials, age, environment, traffic data and performance.

Results from the assessment of the performance of a sample of relatively old sections of road combined with an assessment of the performance of some of the new sections to date will provide important information for developing guidelines for the selection of the most suitable solutions for many of the road building problems encountered in Mozambique.

The project will make a significant contribution to the suite of specifications and work norms which are being developed by TRL under the RRIP/AFCAP project. It will harmonise the on-going preparation of work norms and guidelines with the results of the back analysis of the performance of the older road sections.

3 Report Objectives

This report covers the inception of this phase of the overall project. This phase is entitled, '*Analysis of Performance of Previous Low Volume Rural Roads in Mozambique*'. The results of this analysis will provide additional research data to feed into the current development of specifications, work norms and guidelines for the provision of low volume surfaced roads (LVSRs) in Mozambique.

The objectives will be achieved through four main activities:

- Preliminary activities, including site visits and desk study of historical projects.
- Field investigations involving measurements of the current condition of the roads and collection of samples for testing in the laboratory.
- Laboratory testing of materials.
- Analysis of test results and reporting.

4 Project Organisation

4.1 Project Team

Phase 4 of the project utilises some of the arrangements that were put in place for Phases 1 to 3. The structure of the team and responsibilities has changed from Phase 1 as shown in Table 4-1.

Table 4-1 Local team structure

| Position | Role |
|---------------------------|---|
| Maintenance Director | Directing the research, liaising at higher levels in ANE and between ANE and TRL. Providing guidance and advice to the project in line with the RRIP objectives. |
| Head of Maintenance Dept. | Managing execution and evaluation of the project. |
| ANE Project Coordinator | Coordination of project activities at National Level, supervision of works. Collaboration with TRL Team in relation to the management of the project. Participating in the actual fieldwork and data management |
| Director of Projects | Responsible for preparing and coordinating the laboratory testing programme in collaboration with TRL and Maintenance Director. |
| Provincial Delegacaos | These will contribute to the project with local experience, field surveys, recording and collation of data, participating in data analysis in collaboration |

| | |
|--|--|
| <ul style="list-style-type: none"> • Maputo Province: • Inhambane Province: • Zambezia Province: • Nampula Province: • Cabo Delgado Province: • Niassa Province: | <p>with TRL Team within each province as follows:</p> <p>Marracuene-Ferroviano and Boane-Limbombos Road</p> <p>Pambara-Rio Save Road</p> <p>Rio Zambezi-Nocoadala and Quelimane-Namacurra Roads</p> <p>Nametil-Angoche Road</p> <p>Oasse-Mocemboa da Praia Road</p> <p>Mainamba-Metangula and Mandimba-Lichinga Road</p> |
| Provincial Consultants and Contractors | Through the respective Provincial Delegados, responsible for assisting in providing as-built and maintenance information and taking part in reconnaissance and detailed surveys. |
| Other Third Parties | Responsible for providing relevant data, e.g. rainfall data from the Met Office. |

The team is headed by the Director of Maintenance who oversees the project and is the centre of liaison at higher levels. The Head of Maintenance manages the execution of the project while the day to day running of the project lies with the ANE Project Coordinator, Rubina Normahomed. The AFCAP coordinator is assisted by the Provincial Delegados covering the respective Provinces where the projects are located. In addition, the Provincial consultants and contractors, through the Provincial Delegados, assist in providing as built and maintenance information as well as participating in reconnaissance and detailed surveys.

5 Project Scope

The main aim of the overall project is to produce recommendations for specifications and work norms for low volume roads in Mozambique. These will be based on the results of the trials and demonstrations constructed during the previous 3 phases of projects. However, these trials are relatively new and therefore their long term behaviour will not be validated.

The scope of the work to be carried out under this project (Phase 4) is designed to supplement the results obtained in Phases 1 to 3 with long term performance data from sections of road that were built many years ago using similar techniques but whose performance has never been evaluated. This endeavour will increase the volume of data and will make the analysis statistically more reliable.

The project includes the following tasks

- a) Training of local personnel through involvement in all aspects of the project, i.e.
 - i) Setting up of research projects
 - ii) Fields surveys and investigations
 - iii) Data collection and collation
 - iv) Analysis and presentation of results
 - v) Developing specifications
- b) The selection and investigation of road sections for use in the study. It was initially intended, in accordance with the Terms of Reference, that 5 roads be selected in 5 provinces. Selection of the road sections will depend on:
 - i) The level or extent of deterioration
 - ii) The pavement structure
 - iii) The materials used
 - iv) The level of traffic
 - v) Previous maintenance carried out

Following initial reconnaissance (reviewing 9 roads in 6 provinces), a total of 7 roads have been selected in 6 provinces, comprising a total of 20 road sections. These are described in detail in Section 7 of this report, and also summarised in Table 9-1.

The condition and performance of the roads will be investigated. Most of them are categorised as low volume roads.

The pavement construction types to be covered by the study included the following:

- A) Surfacing
 - i) Double surface dressing (DSD)
 - ii) Otta seals
 - iii) Sand seals and other surface treatments
- B) Road bases
 - iv) Emulsion treated bases (ETB)
 - v) Untreated sand bases
 - vi) Unconventional bases such as laterites and calcretes

vii) Hot sand asphalt

5.1 Preliminary Activities

The Consultant carried out the following tasks during the Inception Phase:

- 1) A desk study of the selected projects in consultation with the client and agreement on the selection criteria and the initial list of roads to be included in the research. Outputs of the desk study including traffic data, construction reports and rainfall data can be found in Section 6.
- 2) Field visits to finalise the selection of roads and to identify sites for detailed investigations. Section 7 contains information about each of the roads surveyed during reconnaissance visits.
- 3) Development of a field investigation and laboratory testing programme for each site. In tandem with this task, ANE's provincial laboratories were assessed in terms of personnel and appropriate serviceable equipment. A summary of this assessment is in Section 6.2.4 and in Appendix A.
- 4) From the sites studied, five sites were selected that form a representative list to be investigated during the detailed phase of the project. Section 8 provides recommendations for the roads and study sections.
- 5) For the sites selected, investigation procedures and an implementation programme were established. Section 9 comprises a programme of work for the detailed investigations.
- 6) The road classification and information on the historical and current traffic loading on each selected road were obtained. This information is available in Section 6.
- 7) Information on external factors, such as cyclones and rainfall which may have influenced deterioration was obtained. This information is available in Section 6 and Appendix B and C.
- 8) Construction records were obtained from the ANE headquarters and provincial offices for some of the roads (Section 6.2.1).
- 9) Maintenance records from the ANE headquarters and provincial offices were obtained.

5.2 Field Investigations

These investigations will form part of the detailed phase of the project and will include:

- i) Visual condition assessments
- ii) Drainage evaluation
- iii) Rut depth measurements
- iv) Deflection tests to measure the in-situ elastic properties (i.e. the pavements' load spreading properties)
- v) Dynamic Cone Penetrometer (DCP) tests to determine the in-situ layer strengths and thicknesses
- vi) Extraction of cores of the surfacing for testing

- vii) Test pits to obtain in-situ dry density and moisture contents of the pavement layers and samples of the materials for laboratory testing of properties that cannot be obtained from non-destructive testing on site

5.3 Materials Testing

The consultant will conduct a range of laboratory tests, including but not limited to the following:

- i) In situ moisture content.
- ii) Classification: grading (particle size distribution), Atterberg limits, linear shrinkage.
- iii) Compaction: maximum dry density (MDD), optimum moisture content (OMC).
- iv) Strength: CBR (at soaked, OMC and 0.75.OMC).
- v) Bituminous surfacing: binder content, aggregate characteristics, properties of the bitumen aggregate mix, if appropriate.

5.4 Analysis and Documentation

This will comprise:

- i) Collation of raw data ready for pavement analysis.
- ii) Analysis of data.
- iii) Development of performance trends.
- iv) Input of data to the Highway Development and Management Model (HDM-4). The data will be used to calibrate the road deterioration models contained in HDM-4 to represent road deterioration of low volume roads in Mozambique.
- v) Use of HDM-4 to predict future performance of the test sections.
- vi) Draft conclusions and recommendations.
- vii) Proposal of specifications for low volume roads to be incorporated in the manual that will be developed under Phase 2 and Phase 3 of the RRIP/AFCAP Project.

5.5 Reporting

The following reports will be submitted to the client:

- i) An Inception Report covering the preparatory and preliminary works
- ii) Brief monthly progress reports describing activities carried out during the month, a summary of test results obtained, and initial findings and recommendations.
- iii) A Final Report describing all the works undertaken on the project, including the data collected, its analysis and the results obtained.

The Final Report will include conclusions drawn from the work and will provide recommendations on aspects to be adopted and incorporated in the guides and work norms (*normas de execução*) for a range of pavement designs and surfacings for low volume rural roads in Mozambique. These guides will be used by ANE engineers and their consultants tasked with the management of low volume rural roads.

In accordance with the Terms of Reference, the reports will be submitted in English. Translation of these documents from English to Portuguese will, if necessary, be organised separately.

5.6 Transfer of Knowledge

The transfer of knowledge to ANE staff is a key component of this assignment, and therefore ANE staff will participate in all stages of the project. This will contribute to capacity building within ANE and ensure continuity of the project beyond the implementation stage. A one-day workshop will be held in Maputo to disseminate findings of the project to ANE engineers, selected experts in the field and other stakeholders.

6 Progress

TRL commenced work upon signing the contract in July 2012. The inception of the project included the following stages:

- i) Project start up meetings with DFID, Crown Agents and ANE
- ii) Deployment of staff to Mozambique
- iii) Selection of candidate roads in consultation with ANE
- iv) Collection of as-built and maintenance records for the project roads
- v) Collection of climatic data from the Meteorological Office
- vi) Reconnaissance surveys of the projects
- vii) Preparation of the Inception Report
- viii) Ongoing consultation with ANE via meetings and reports
- ix) Full time participation of key ANE personnel at all stages of the project

The Technical Proposal describes the methodology that will be used to conduct detailed surveys on the test sections. At this inception phase, a total of 9 roads in 6 provinces underwent reconnaissance so that the choice of final sections for detailed study would not be restricted.

6.1 Selection of Candidate Roads

The selection of candidate roads was carried out at a strategic level and focussed on roads that had been constructed using non-standard procedures. The selected roads varied in terms of age, construction type, current condition and geographical location. The names of the candidate roads are given in the following section.

6.2 Data Collection

One of the primary tasks carried out during the inception phase of this project was the collection of relevant data from ANE and other third parties for use in the understanding of the construction, maintenance and performance of the selected roads and sites. The sourcing of data from ANE was coordinated by DIMAN, although some direct contact was also made with the respective directorates and provincial delegations to expedite the process. It was not possible to collect all the required information at the time of submitting this report. The data that were sourced and collected is presented below.

6.2.1 *As-Built Data*

It was not possible to collect all the as-built data for the respective projects. The information that was available at the time of writing the report is summarised below:

| PROVINCE | Project | Available Information | Date |
|-----------------|----------------------------|---|--------------|
| MAPUTO | Marracuene-Ferroviano | Progress Report No. 1- Labour Based Section | July 2005 |
| | | Progress Report No. 1- Equipment Based Section | July 2005 |
| | | Tender Document- Labour Based Section | October 2003 |
| | | Tender Document- Equipment Based Section | October 2003 |
| MAPUTO | Boane-Limbombos- Goba | No Information received to date | |
| INHAMBANE | Pambara-Rio Save | Limited Information Mix design charts | |
| ZAMBEZIA | Rio Zambezi- Nicoadala | No Information received to date | |
| | Quelimane- Namacurra | | |
| NAMPULA | Nametil-Angoche | Project completion Report- Vol.1 and 2 | June 2007 |
| CABO DELGADO | Oasse-Mocemboa da Praia | No Information | |
| NIASSA | Maniamba- Metangula | Final Report | 2008 |
| NIASSA | Mandimba-Lichinga | Works Completion Report | 2008 |

6.2.2 *Maintenance Records*

Maintenance records were still unavailable from DIMAN and the provinces at the time of producing this report. The information collected will be used in the detailed phase of the study.

Information obtained during preliminary enquiries suggests that only routine maintenance that includes pothole patching, grass cutting and drain clearing was carried out (excluding crack sealing). No periodic maintenance such as reseals was carried out and neither was any rehabilitation executed on any of the candidate roads. More information will be provided in due course and may be incorporated in the progress report for the month of October.

6.2.3 *Deflection Data*

ANE carried out a nationwide deflection testing exercise on all sealed roads in 2010. The survey was designed to determine pavement strengths for the different sections of road for planning purposes. These data were sought from ANE for the assessment of the sections that will be earmarked for research. The data and information will be used in a number of ways:

1. The pavement deflection data will be used to determine uniform sections in terms of pavement stiffness. Pavement stiffness has a direct influence on performance and this will be an important parameter in the development of specifications for low volume roads.
2. The pavement stiffness values from the deflection data will be used with the DCP test data to determine the adequacy of the pavement structures for the traffic.

The deflection data has been supplied by ANE from the FWD measurements. However, the data is not appropriate for use in the project because the tests were carried out at 10km intervals, which is too wide. Some of the selected sections are 5km long or less. This means that, by chance, there could be only one test result in the whole segment of road selected for investigation under this project. Consequently, further deflection tests will need to be carried out as part of the planned field surveys. There are two options available:

1. There exists a Benkleman Beam at ANE and this could be used to carry out the deflection tests. This test is more laborious and slow but feasible. This test requires a hired lorry to provide the wheel loading.
2. There is a PRIMA at TRL UK which can be shipped to Mozambique and is used to determine pavement stiffness though it does not give data that is as elaborate as that provided by the FWD.

6.2.4 Laboratory capacities to carry out surveys and testing

Inquiries were made into the capability of ANE, in terms of equipment and personnel, to carry out field investigations and laboratory testing. Standard questionnaires were distributed to the provincial laboratories through the project co-ordinator. The responses received showed that the laboratories generally had the equipment and personnel to carry out soil and aggregate testing. However, all the laboratories did not have the capacity to carry out the following:

- Triaxial tests because it is not a commonly used test method to assess the strength or suitability of material for pavements in Mozambique.
- Bitumen tests.
- In situ density tests using nuclear density devices due to the non-availability of equipment.

In addition to the above, the following observations were also made:

- The laboratory in Niassa has only one member of staff. This falls short of the staff complement required to carry out both field investigations and laboratory testing.
- The equipment in some of the laboratories needs calibration. This requires some of the equipment to be shipped to South Africa and then back into the country again, because the calibration equipment is bulky and cannot be undertaken in situ.
- Some of the laboratory staff are involved in on-going projects within the respective provinces. This leaves them with limited availability to participate in this project.

The capacity of the ANE laboratories to carry out the tests is summarised in Appendix A.

6.2.5 Traffic Data

Traffic data were obtained from the client for all the roads except the unclassified Marracuene-Ferruviario road. There was limited time to review the data at the inception stage and hence the data will be used during the detailed investigation phase of the project. The summary Annual Average Daily Traffic (AADT) data are contained in Table 6-1.

Data on traffic loading in terms of equivalent standard axle (ESAs) is not available but efforts will be made to carry out snapshot axle load surveys during the detailed field surveys. It is possible to use a portable weighbridge or weigh pad for this purpose. Weighbridges have been identified at some sites on the trunk roads and axle load data can be extracted during detailed investigations. On minor roads, portable weigh pads will be used. This information is important in that the traffic could consist of a large number of light vehicles which have very low damaging factors on the pavement thus the AADT by itself does not give the full picture of the traffic loading.

In the case that it is not possible to measure axle loads, information will be sought from ANE on standard values of loading for different categories of vehicles.

6.2.6 Rainfall Data

Rainfall data were obtained from the Meteorological Office. The data were for the stations that were identified as being closest to the respective projects. The data consisted of annual rainfall, maximum rainfall for each month and details of any unusual or severe conditions that prevailed, such as floods. All the data were collected for the period 2006 to 2012.

Mozambique is experiencing climate change with the recurrence of adverse weather including tropical storms and cyclones which hit the coastal and some inland areas several times a year. A summary of the major cyclones was obtained from the Meteorological Department and is given in Table 6-1 and Appendix B.

The information on precipitation during adverse weather was also procured from the Meteorological Department. This is the maximum annual daily rainfall in mm shown in Table 6-1 and Appendix C. This shows the magnitude and intensity of rainfall which has had significant influence on the performance of the roads. During the rainy season of 2012, flood damage reached US\$18 million.

Table 6-1 Key data for candidate roads

| Province | Road No. | Road Name | Length (km) | Year of Construction | Contractor | Consultant | Type of Surface | Type of Base | Design/ Construction documents | Maintenance records | Traffic (2011 AADT) | Annual Average Rainfall (mm) (1996-2011) | Station |
|--------------|--------------|--------------------------------|-------------|----------------------|--------------------|----------------|-------------------------|--|----------------------------------|---------------------|---|--|-------------------|
| MAPUTO | Unclassified | Marracuene - Ferroviario | 2 | 2005 | CETA | Africon | Sand Seal | Emulsion Treated Sand Base | Method statement/ specifications | No Information | | 806 | Marracuene |
| MAPUTO | R400 | Boane- Pequeno Limbombos- Goba | 3 | No Information | | | Double Surface Dressing | Crushed rock/cement treated base | No Information | No Information | 1,197 | No Information | |
| INHAMBANE | N1 | Panbarra - Rio Save | 13 | 2009 | CETA | Stange | Hot Sand Asphalt | Patched Double Surface Dressing on cement treated base | Design Charts | No Information | 538 | 532 | Vilanculos |
| ZAMBEZIA | N1 | Nicoadala - Rio Zambezi | 1.8 | | | | Hot Sand Asphalt | Crushed stone | No Information | No Information | 512 (Rio Zambezi) 548 (Rio Luala) 864 (Nicoadala) | 894 | Caia |
| ZAMBEZIA | N10,N11 | Quelimane - Namacurra | 5.2 | | | | Hot Sand Asphalt | Macadam | No Information | No Information | 1975 (Quelimane) 1185 (Namacurra) | 1,288 | Quelimane |
| NAMPULA | N104 | Nametil - Angoche | 7.2 | 2007 | CETA/CMC JV | Black & Veatch | Sand cover on Otta Seal | Laterite | Completion Report | No Information | 229 | 1,089 | Nametil |
| CABO DELGADO | N380 | Oasse - Mocimboa da Praia | 3.1 | 2001 | OPCE/MOTA | CPG/CPP | Sand Seal | Emulsion Treated Sand Base | No Information | No Information | 218 | 1,279 | Mocimboa da Praia |
| NIASSA | N13 | Lichinga - Mandimba | 13 | 2005 | CMC Africa Austral | ANE | Otta Seal | Natural Gravel | Completion Report | No Information | 290 (Lichinga) 80 (Mandimba) | 1,279 | Lichinga |
| NIASSA | N361 | Manianba - Metangula | 12 | 2008 | CMC Africa Austral | ANE | Otta Seal | Natural Gravel | Project Progress Report | No Information | 55 | 1,279 | Lichinga |

Traffic data obtained from the 2011 ANE Traffic Data Report

6.3 Selection of Sub Sections

The criteria that were adopted at the beginning of the project in order to select the sub sections for each road were:

- Classification of road
- Traffic
- Age of road
- Construction type
- Availability of construction and maintenance records
- Current pavement condition
- Most importantly, the local knowledge and expertise of the ANE staff were also decisive in the identification of the candidate roads.

7 Details of the Road Sections

7.1 General

A reconnaissance survey was undertaken to identify a range of study sections in the six provinces. A map of Mozambique and the locations of the road sections is included in Appendix D.

The detailed characteristics of the road sections are presented below. This is based on the as-built and maintenance data (if available) that were collected, together with the observations and assessments that were carried out as part of the reconnaissance survey. For the purposes of referencing the road sections, a datum was selected and marked with paint, and the GPS locations were recorded. The chainages of each section were marked from this datum.

7.2 Classification of Road Condition

The classification of the road condition was based on the visual observation relating to the following road characteristics in

Table 7-1:

- Ride quality
- Extent of potholes
- Extent of cracking
- Rutting.

Table 7-1 Road condition criteria

| Road Condition | Riding Quality | Surface Condition | Potholes | Cracks | Base |
|----------------|-------------------|---------------------------|----------|---|--|
| Good | Good | No surfacing loss | None | Minor, localised, sealed | Intact, not visible through the surfacing; |
| Fair | Slight Discomfort | Surfacing loss noticeable | 5 % | Minor but extensive (reflective, on wheel paths, edge of carriageway) | Not visible, through the surfacing but visible on edge drops |

| | | | | | |
|-----------|------------------------|--|--------|---|--|
| Poor | Significant Discomfort | Surfacing loss extensive | 5%-10% | Major and extensive (reflective, on wheel paths, edge of carriageway) | Visible through the surfacing and edge drops |
| Very Poor | Severe Discomfort | Complete surfacing loss/traffic avoiding running lane, requires reconstruction | >10% | Ravelling and Disintegration | Disintegration; traffic avoiding running lane, requires reconstruction |

7.3 Maputo

7.3.1 Marracuene – Ferroviario Road (Unclassified)

This is an unclassified road in Maputo province that offers an alternative route to the N1 to Maputo City and Marracuene. The road is about 27km long and was constructed in 2005 using sand seal on an emulsion-stabilised sand base.

Four study sections were identified on this road, having a combined length of 2km. They were constructed in the year 2005. There are no maintenance or traffic data available for this road. However, site observations show that it is heavily trafficked by light to medium trucks which mainly serve as public transport. The alignment is generally flat and straight. The sections are generally in poor condition, and are characterised by several potholes and cracks. The finished road level is generally below ground level, and appears to be poorly drained along the entire project extent.

Details of the study sections are given in Table 7-2 and typical views of the sections are given in Figure 7-1.

Table 7-2 Properties of study sections

| | |
|--------------------|-----------------------------|
| PROVINCE | Maputo |
| Road Name | Marracuene-Ferruviario Road |
| Road Length | 27 km |

Emulsion treated base ETB

DATUM: Marracuene

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|----------------|----------------|-------------------------------------|--|--|---|---------------------------------------|
| 1 | Km: 0+000 | 0+300 | 0.3 | Sand seal | ETB | Poor | Flat | Trough | Good | Road level below natural ground level |
| 2 | Km: 0+300 | 0+900 | 0.6 | Sand seal | ETB | Fair | Flat | Trough | Good | Road level below natural ground level |
| 3 | Km: 2+800 | 3+000 | 0.2 | Sand seal | ETB | Poor | Flat | Trough | Good | Road level below natural ground level |
| 4 | 3+800 | 4+100 | 0.3 | Sand seal | ETB | Poor | Flat | Trough | Good | Road level below natural ground level |

The surface condition of Section 1 is poor with several potholes and surface loss. Section 2 is better than Section 1 but most traffic tends to drive on the sandy side of the road which is smoother.

Section 3 is identical in condition to Section 1. The surface has several potholes and depressions by the side of the surfaced portion where water ponds.

Section 4 has deeper and wider potholes and traffic generally avoids using the road section and rather uses the side of the road. It is in very poor condition.



Section 1



Section 2



Section 3



Section 4

Figure 7-1 Typical Sections of the Marracuenne – Ferroviario Road

Although this road was built in 2005, it is already showing signs of significant structural and surfacing failure. The causes of the failure will be investigated during the detailed phase of this study. This could be attributed to some of the following:

1. Under design of the pavement
2. Non-compliance with the method statement during construction
3. Drainage induced failure associated with the road level being below ground level
4. Seasonal moisture variations/repeated wetting and drying.

7.3.2 Boane – Limbobos – Goba Road (R400)

This road connects Boane, which is approximately 40km south-west of Maputo along the N2, to the Limbobos dam and on further south-west towards the town of Goba at the Mozambique-Swaziland border. The total length of the road is about 45km. Information on the age, construction and maintenance of this road was not available at the time of preparing this report.

The study sections identified during the reconnaissance survey have a combined length of about 3km, and are representative of the condition and materials of the road.

There are two different pavement constructions on the road. From Boane to Rio Umbuluzi the road comprises a double surface dressing on a stone macadam base, and from Rio Umbuluzi to the Limbombos dam it comprises a double surface dressing on a cement-stabilised sand base. The two sections are separated by a bridge (currently collapsed) over the river. The general terrain is undulating and mostly straight. Most of the road is still in good condition and functioning well but sections exist that are visually in fair or poor condition. The road crosses swamps in some locations.

Details of the study sections are summarised in Table 7-3 and views of the study sections are given in Figure 7-2.

Table 7-3 Properties of study sections

| | |
|--------------------|----------------------|
| PROVINCE | Maputo |
| Road Name | Boane-Limbombos-Goba |
| Road Length | 45 km |

Double surface dressing DSD

DATUM: Boane

Cement treated base CTSB

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|-------------------------|----------------|-------------------------------------|--|--|---|--------------------------------------|
| 1 | Km: 0+000 | 0+300 | 0.3 | Double Surface Dressing | Crushed Rock | Good | Flat | Crest | Good | No side drains exist but kerbs exist |
| 2 | Km: 0+300 | 0+800 | 0.5 | Double Surface Dressing | Crushed Rock | Poor | Slope | Flat | Good | Potholes, Cracks and Patching |
| 3 | Km: 4+700 | 5+100 | 0.4 | Double Surface Dressing | CTSB | Good | Flat | Flat | Good | |
| 4 | Km: 5+400 | 5+700 | 0.3 | Double Surface Dressing | CTSB | Fair | Flat | Flat | Good | Cracks all over but minor potholing |
| 5 | Km: 7+700 | 7+960 | 0.3 | Double Surface Dressing | CTSB | Good | Slope | Crest | Poor | Minor Rutting |
| 6 | Km: 7+960 | 8+600 | 0.64 | Double Surface Dressing | CTSB | Poor | Flat | Crest | Poor | Rutting, Cracking and Potholes |

Section 1 and 2 were constructed with a crushed stone Macadam base. Section 1 is in good condition despite being predominantly flat and without side drains. Section 2 is visually in poor condition with several potholes and cracks. The geometry of this section alternates between flat and sloping. Sections 3 to 6 were built with a cement treated sand base (CTSB). Section 3 is flat and the visual condition is good. Section 4 is in fair condition with several crocodile cracks and minor potholing. Section 5 is sloping and is located in a swamp. The visual condition is good with minor rutting. Section 6 is located in a swamp but, unlike Section 5, the condition is poor with significant rutting, cracking and potholing.



Section 1



Section 2



Section 3



Section 4



Section 5



Section 6

Figure 7-2 Typical Sections of the Boane – Limbombos – Goba Road

7.4 Inhambane

7.4.1 Pambarra – Rio Save Road (N1)

This road starts at the Pambarra junction at the turn-off to Vilanculos and continues up to the Rio Save. It is a segment of about 121km on the main trunk road N1. The construction consists of hot sand asphalt (HSA) surfacing laid on patched double surface dressing which was laid on a cement treated base and sub-base.

There are 15 study sections, with a combined length of 13km, which were built in 2009 as a maintenance treatment for portions of the road that were highly distressed; the original dressing had developed several deep potholes at these locations.

Most of the sections are flat terrain, although a few sections have horizontal curves, most of which are built on embankments. Visually, all the sections are in good condition with only very minor cracks, no potholes and no ruts.

The sections built on embankments do not have any visible evidence of surface drainage. However sub-surface drainage may be a problem in areas where the embankments were built in swamps.

Details of the study sections are given in Table 7-4 and typical views of the sections are given in Figure 7-3.

Table 7-4 Properties of study sections

| | |
|--------------------|------------------------|
| PROVINCE | INHAMBANE |
| Road Name | Pambara - Rio Save (1) |
| Road Length | 121 km |

Double surface dressing DSD

Cement treated base CTB

DATUM: Vilanculos Junction

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drain (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|------------------|--------------------|-------------------------------------|--|--|--------------------------------------|--|
| 1 | Km: 17+900 | 19+200 | 1.3 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | |
| 2 | Km: 22+200 | 23+700 | 1.5 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | 7m wide, minor pitting, pronounced edge drop |
| 3 | Km: 48+600 | 49+600 | 1 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | Mix seems stiffer than S1 and S2 |
| 4 | Km: 50+000 | 50+200 | 0.2 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | Junction to Inhasorro, DSD Scraped off first |
| 5 | Km: 50+400 | 50+600 | 0.2 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | Junction to Inhasorro, DSD Scraped off first |
| 6 | Km: 57+900 | 58+500 | 0.6 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | |
| 7 | Km: 69+300 | 69+600 | 0.3 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | |
| 8 | Km: 69+800 | 69+900 | 0.1 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | |

| | |
|--------------------|------------------------|
| PROVINCE | INHAMBANE |
| Road Name | Pambara - Rio Save (2) |
| Road Length | 121 km |

Double Surface Dressing DSD

Cement Treated Base CTB

DATUM: Vilanculos Junction

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|-----------------|----------------|--------------|---------------------|------------------|--------------------|-------------------------------------|--|--|---|--|
| 9 | Km: 70+200 | 70+800 | 0.6 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | Curve |
| 10 | Km: 74+900 | 75+600 | 0.7 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | |
| 11 | Km: 76+100 | 76+900 | 0.8 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | |
| 12 | Km: 93+900 | 94+600 | 0.7 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | Low lying but elevated prone to flooding |
| 13 | Km: 104+000 | 105+600 | 1.6 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | Curve, low lying + straight |
| 14 | Km: 106+500 | 108+000 | 1.5 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | Straight then more elevated curve |
| 15 | Km: 110+500 | 112+400 | 1.9 | Hot Sand Asphalt | Patched DSD on CTB | Good | Flat | Crest | Good | Curve straight |
| SAND BORROW PIT | Km: 43+600 | | 0 | | | | | | | On RHS towards Rio Save |

The sections have very similar characteristics but with minor differences. There is some minor pitting in Section 1; the mix on Section 3 looks leaner; Section 12 is low lying; and there are curves on Sections 13, 14 and 15.



Section 3



Section 7



Section 12



Section 13

Figure 7-3 Typical Sections of the Pambarra – Rio Save Road

7.5 Zambezia

7.5.1 Rio Zambezi – Nicoadala Road (N1)

This road connects Rio Zambezi to the junction at Nicoadala. The road is about 150km long and passes through mainly undulating terrain.

There are 6 sections of hot sand asphalt (HSA) surfacing that were identified as potential candidates for the detailed study. The total length of these sections is 1.75km. These sections were built as a maintenance treatment for spots on the road that had developed significant distress. There are no data available on the age of the road, although it is described as 'very old' by ANE. The pavement structure consists of hot sand asphalt on patched asphalt on cement treated base and sub-base.

Some of the sections lie in swampy low-lying land and others are on a hill crest with no visible sub-surface drainage problems.

Visually the condition of the sections varies between good, fair and poor with significant rutting and cracking noticed in the poor sections.

Details of the study sections are given in

Table 7-5 and typical views of the sections are given in Figure 7-4.

Table 7-5 Properties of study sections

| | |
|--------------------|-------------------------|
| PROVINCE | ZAMBEZIA |
| Road Name | Rio Zambezi - Nicoadala |
| Road Length | |

Double surface dressing DSD

DATUM Rio Zambezi

Cement treated base CTB

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|------------------|----------------------------------|-------------------------------------|--|--|---|---|
| 1 | Km: 42+700 | 42+810 | 0.113 | Hot Sand Asphalt | Patched on CTB after milling DSD | Good | Slight Slope | Crest | Good | |
| 2 | Km: 48+200 | 48+300 | 0.064 | Hot Sand Asphalt | Patched on CTB after milling DSD | Good | Slight Slope | Flat | Good | No Sealed Shoulders |
| 3 | Km: 105+000 | 105+170 | 0.17 | Hot Sand Asphalt | Patched on CTB after milling DSD | Good | Slope approaching low lying | Flat | LHS Swamy with rice growing | High embankment |
| 4 | Km: 105+500 | 105+600 | 0.09 | Hot Sand Asphalt | Patched on CTB after milling DSD | Good | Flat | Trough/Cut | Good | |
| 5 | Km: 140+700 | 141+900 | 1.2 | Hot Sand Asphalt | Patched on CTB after milling DSD | Fair | Flat | Crest | Good | Low lying land, though well drained. Some cracks and 5 potholes |
| 6 | Km: 155+000 | 155+200 | 0.2 | Hot Sand Asphalt | Patched on CTB after milling DSD | Poor | Flat | Crest | Good | Crocodile cracks, rutting and flow. |

Sections 1 and 2 are on a longitudinal slope. They show no significant defects and appear to be in good condition despite there being no sealed shoulders. Section 3 is also on a longitudinal slope but, unlike Sections 1 and 2, is in a swampy location with some of the side drains waterlogged. Despite this it appears to be in good condition. Section 4 is flat and lies at the bottom of the slope. It also appears to be in good condition. Section 5 is similar to Section 4 but the visual condition can be described as fair showing cracking and minor potholing. Section 6 is also flat but it shows significant cracking and rutting.



Section 3



Section 5



Section 6

Figure 7-4 Typical Sections of the Rio Zambezi – Nicoadala Road

7.5.2 Quelimane – Namacurra Road (N10)

This road is part of the trunk road N10. It connects the city of Quelimane to the junction at Nicoadala. The road is about 30km long and passes through mainly level but low-lying terrain characterised by swamps. The construction consists of four sections of hot sand asphalt (HSA) surfacing that was applied as a maintenance alternative to the conventional asphalt concrete strengthening overlay. The HSA overlay was applied on a pavement originally comprising a double surface dressing (DSD) overlying a crushed stone base, natural gravel sub-base and embankment fill in that order. The average height of the embankment is 2m and is waterlogged on most of the sections. Five study sections with a total length of 5.2km were surveyed.

Visually the sections all appear to be in good condition with only minor differences in surface appearance between them.

Details of the study sections are given in Table 7-6 and typical views of the sections are given in Figure 7-5.

Table 7-6 Properties of study sections

| | |
|--------------------|-----------------------|
| PROVINCE | ZAMBEZIA |
| Road Name | Quelimane - Namacurra |
| Road Length | |

DATUM Quelimane

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|------------------|----------------|-------------------------------------|--|--|---|---|
| 1 | Km: 6+000 | 7+400 | 1.4 | Hot Sand Asphalt | Macadam | Good | Flat | Crest | Embankment in Swamp | |
| 2 | Km: 7+400 | 8+600 | 1.2 | Hot Sand Asphalt | Macadam | Good | Flat | Crest | Embankment in Swamp | Visible difference in Mix |
| 3 | Km: 1 6+900 | 18+000 | 1.1 | Hot Sand Asphalt | Macadam | Good | Flat | Crest | Embankment in Swamp | Extra layer of HSA on surfaced shoulders |
| 4 | Km: 21+300 | 21+900 | 0.6 | Hot Sand Asphalt | Macadam | Good | Flat | Crest | Embankment in Swamp | |
| 5 | Km: 26+500 | 27+400 | 0.9 | Hot Sand Asphalt | Macadam | Good | Flat | Crest | Embankment in Swamp | Minor deformations on inside of curve as bridge is approached |
| 6* | 0+000 | | | | | | | | | In Quelimane City |
| 7* | 61+000 | | | | | | | | | Sub-base borrow pit on theLHS towards Rio Zambezi |
| 8* | 51+000 | | | | | | | | | Sand from Rio Licuari on LHS towards Rio Zambezi |

* Borrow pit sites



Section 1

Figure 7-5 Typical sections of the Quelimane – Namacurra Road

7.6 Nampula

7.6.1 Nametil-Angoche Road (N104)

This road links the provincial city of Nampula to the port city of Angoche. It was built as part of the Rural Roads Rehabilitation Programme in 2007. The entire road consists of alternating paved and unpaved sections, approximately 63km in length. However, the reconnaissance survey was limited to the paved sections

The construction of the paved sections consisted of a single Otta seal with a sand cover seal surfacing on a cement stabilised base overlying a lateritic and granular sub-base.

Concrete lined side drains were also constructed at locations that are at risk of erosion by runoff. Improvements to drainage also included the re-excavation of silted mitre drains and the construction of new ones.

As part of the rehabilitation, three trial sections of variable lengths were constructed as follows:

1. Ch 14+800-14+900 (100m) single Otta seal with no sand cover seal on a natural base material
2. Ch 27+400-27+500: Two sections of prime at different consistencies on a gravel wearing course (to determine the effects of the prime in increasing the durability of the surfacing). However, this trial section lies within the unpaved section of the road and therefore does not form part of the study sections.

Five study sections, with a combined length of 7.2km were identified. The study sections lie on terrain that ranges from flat to rolling. They do not show any visible signs of failure apart from isolated sections, most of which are at the interfaces of the paved and unpaved sections. The road generally lies above the natural ground level and is in good condition.

Details of the study sections are given in Table 7-7 and typical views of the sections are given in Figure 7-6.

Table 7-7 Properties of study sections

| | |
|--------------------|-----------------|
| PROVINCE | Nampula |
| Road Name | Nametil-Angoche |
| Road Length | 63 km |

Cement treated base CTB

DATUM Nametil

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|----------------|----------------|-------------------------------------|--|--|---|---------------|
| 1 | 0+000 | 2+500 | 2.5 | Otta seal | CTB | Good | Rolling | Crest | Good | N/A |
| 2 | 3+600 | 3+800 | 0.2 | Otta seal | CTB | Good | Rolling | Flat | Good | N/A |
| 3 | 4+000 | 5+000 | 1 | Otta seal | CTB | Good | Rolling | Flat | Good | N/A |
| 4 | 9+000 | 10+500 | 1.5 | Otta seal | CTB | Good | Rolling | Flat | Good | N/A |
| 5 | 11+700 | 13+700 | 2 | Otta seal | CTB | Good | Rolling | Flat | Good | N/A |



Section 1



Section 2



Section 3



Section 4

Figure 7-6 Typical sections of the Nametil-Angoche road

7.7 Cabo Delgado

7.7.1 Oasse-Mocimboa da Praia Road (N380)

This road connects Pemba to Mocimboa da Praia via Sunate on the N1 and Macomia. The road is approximately 43km long. The longitudinal alignment ranges from flat to rolling, whilst the cross sections range from full cutting, partial cutting/filling to full embankment.

The road was constructed in 2001 using an emulsion treated sand base (ETB) overlaid by a sand seal surfacing. However, more details of the as-built and maintenance information for this road were not available at the time of producing this report.

Eight study sections with a combined length of 3.1km were identified. Visually, the road condition ranges from good to very poor. The sections in good condition are located where the road level generally lies above ground level. Sections in poor condition are at locations where the road level lies below the ground level and where the road lies within partial or full cutting. Typical defects observed on the study sections include rutting on the wheel paths, cracking, potholes and surface stripping and disintegration.

Details of the study sections are given in Table 7-8 and typical views of the sections are given in Figure 7-7.

Table 7-8 Properties of study sections

| | |
|--------------------|-------------------------|
| PROVINCE | Cabo Delgado |
| Road Name | Oasse-Mocimboa da Praia |
| Road Length | 43 km |

Emulsions treated base ETB

DATUM Oasse

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|----------------|----------------|-------------------------------------|--|--|---|---|
| 1 | Km: 0+000 | 0+300 | 0.3 | Sand Seal | ETB | Fair | Flat | Crest | Good | Block cracks-(shrinkage) unsurfaced shoulders Road level above ground level |
| 2 | Km: 0+300 | 0+900 | 0.6 | Sand Seal | ETB | Poor | Flat | Flat | Good | Potholes (1.5x0.5m) Transverse cracks Stripping Road level below ground level |
| 3 | 2+000 | 2+500 | 0.5 | Sand Seal | ETB | Poor | Slope | Flat | Good | Potholes Rutting on Mocimboa bound wheel track Road level at ground level |
| 4 | 2+800 | 3+100 | 0.3 | Sand Seal | ETB | Good | Slope | Flat | Good | |
| 5 | 20+800 | 21+300 | 0.5 | Sand Seal | ETB | Very Poor | Rolling | Crest | Poor | Road level below ground level |
| 6 | 22+100 | 22+500 | 0.4 | Sand Seal | ETB | Good | Slope | Crest | Poor | Road level above ground level |
| 7 | 22+500 | 22+800 | 0.3 | Sand Seal | ETB | Poor | Flat | Crest | Poor | Potholes Cracks Surface Disintegration Failure mainly on Mocimboa bound lane where water ponds in cutting Road level below ground level Cut and fill cross section |
| 8 | 22+800 | 23+000 | 0.2 | Sand Seal | ETB | Poor | Low lying | Crest | Poor | Rutting, Cracking and Potholes Road level above ground level |

Sections 1 and 2 are on flat terrain, the road lies above ground level and appears well drained. Section 1 is in a fair condition and most of the visible defects are block cracks.

Section 2 is in poor condition as characterised by the stripping of the surfacing, transverse cracks and severe potholing (typically 1.4m by 0.5m), which are mainly concentrated in the Oasse-bound lane.

Section 3 is on a sloping alignment and the road level is generally below ground level. The condition of this section is poor and is characterised by block cracking, potholes and rutting, which is mainly localised in the outer wheel path of the Mocimboa-bound lane.

Section 4 is on a longitudinal slope. The road level is above ground level and it is in good condition. Section 5 is in rolling terrain and the cross section is in part cut and part fill. The condition of the section is very poor, most evident in the cutting on the Mocimboa-bound side of the carriageway where the road lies below the natural ground level. There is no evidence of sub-surface drainage. The typical depth of edge drops is 300mm.

Section 6 is on a longitudinal slope and the road is above ground level. The section is in good condition and the visible defects are block cracks that are localised approximately 1m on either side of the edge of the pavement.

Section 7 is on flat terrain, with most of the road lying below ground level. The section is in poor condition and is characterised by cracking, surface disintegration and potholes. These defects are localised in the Mocimboa da Praia-bound lane. There is no evidence of sub-surface drainage.

Section 8 lies within a low-lying part of the road. However, the road level is elevated approximately 1.5 metres above ground level. The section is in a fair condition. Visible defects are edge drops and cracks, which are localised within 1m of the edges of the pavement.



Section 1 and 2



Section 2



Section 4



Section 5

Figure 7-7 Typical sections of the Oasse-Mocimboa da Praia road

7.8 Niassa

7.8.1 Maniamba-Metangula Road (N361)

This road connects Lichinga, the provincial capital, to the town of Metangula on the shores of Lake Niassa. The total length of the road is approximately 30km. The terrain varies from rolling to mountainous.

The road construction comprises an Otta seal with a sand cover seal on a natural base and sub-base.

Although the construction of the road is the same, there are two distinct sections, each approximately 14km long. The differences between the distinct sections are the age and general condition of the pavement

The recently constructed section was constructed in 2008 and consists of the 14km section between Metangula and halfway to Maniamba. It contains sub-sections that are variable in terms of terrain and pavement condition. The terrain ranges from flat to mountainous, whilst the pavement condition ranges from good to very poor.

The older section lies in terrain that ranges from low to mountainous. Information on its construction and maintenance are not available but further enquiries are being made.

There are nine study sections, with a combined length of 14.2km which are located within both the earlier and more recently constructed sections.

Details of the study sections are given in Table 7-9 and typical views of the sections are given in Figure 7-8.

Table 7-9 Properties of study sections

| | |
|--------------------|--------------------|
| PROVINCE | Niassa |
| Road Name | Maniamba-Metangula |
| Road Length | 30 km |

DATUM: Metangula

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|----------------|----------------|-------------------------------------|--|--|---|--|
| 1 | 0+000 | 2+500 | 2.5 | Otta seal | Natural Gravel | Good | Flat | Flat | Good | Road is in urban area Programme for paving all drains in urban area ongoing Accumulation of sand in Lichinga bound lane-possibly due to runoff |
| 2 | 2+500 | 2+600 | 0.1 | Otta seal | Natural Gravel | Poor | Flat | Flat | Good | Potholes Cracking Access to petrol station |
| 3 | 3+600 | 3+800 | 0.2 | Otta seal | Natural Gravel | Poor | Slope | Flat | Good | Potholes Rutting Road level at ground level |
| 4 | 4+000 | 5+000 | 1 | Otta seal | Natural Gravel | Good | Slope | Flat | Good | |
| 5 | 0+000 | 0+200 | 0.2 | Otta seal | Natural Gravel | Fair | Rolling | Crest | Poor | Road level below ground level |
| 6 | 0+200 | 4+100 | 3.9 | Otta seal | Natural Gravel | Very Poor | Slope | Crest | Poor | Road level above ground level |
| 7 | 4+100 | 6+900 | 2.8 | Otta seal | Natural Gravel | Poor | Flat | Crest | Poor | Potholes Cracks Surface Disintegration |
| 8 | 9+000 | 10+500 | 1.5 | Otta seal | Natural Gravel | Fair | Low lying | Crest | Poor | Rutting, Cracking and Potholes Road level above ground level |
| 9 | 11+700 | 13+700 | 2 | Otta seal | Natural Gravel | Good | Low lying | Crest | Poor | Rutting, Cracking and Potholes Road level above ground level |

Section 1 is 2.5km long and lies wholly within the urban area of Metangula. The longitudinal alignment is straight and the vertical alignment is generally flat. There are a number of culverts that collect water from the mountainous (Maniamba/Lichinga-bound) side of the carriageway and this water is discharged to the land which is adjacent to the Metangula-bound side of the road.

The study section is in good condition and is characterised by the following:

- Sand on carriageway on the mountainous side of the road cross section. It is not clear whether this sand accumulation is a result of runoff overtopping.
- Paved drains on the upstream side of the watercourses/low-lying areas. The programme of paving the side drains is on-going.

Section 2 is 0.1km long and is located approximately 2.5 km from Metangula. The road lies below natural ground level, and there are signs of poor pavement condition and deterioration characterised by potholes, patching, runoff overtopping and severe cracking and patching.

Section 3 is 0.2km and is located within the mountainous area that the road traverses. The study section is in a poor condition and is characterised by severe cracks and potholes. There is no visual evidence of sub-surface drainage.

Section 4 is 1km long and is in the mountainous area. It is well drained and there is no evidence of any structural or surfacing defects. The study section is in good condition.

Section 5 is 0.2km long and lies within low lying and mountainous terrain. It is in a fair condition and is characterised by crocodile cracking and surface stripping.

Section 6 is 3.9km long and lies within terrain that ranges from flat, low lying to mountainous. The study section is in a very poor condition and is characterised by stripping, disintegration, potholes and complete surfacing disintegration in some areas. The road along this section generally lies in areas where there are deep cuts due to the mountainous terrain. The side drains are not paved and there is no evidence of sub-surface drainage. The absence of sub-surface drainage may have contributed in part to the poor pavement condition. Some localised maintenance work is being carried out on some of the areas with the most severe pavement failures. The work includes pothole repair, drainage improvement and partial to full pavement reconstruction.

Section 7 is 2.8km long and lies in flat terrain. The road level lies above ground level throughout. This study section is in good condition.

Section 8 is 1.5km long and lies within rolling/undulating and low-lying terrain. It is in a fair condition and is characterised by marginal rutting within the wheel paths, cracking and minor potholes.

Section 9 is 2km long and lies within rolling/undulating and low-lying terrain. It is in good condition and is characterised by minor rutting, cracking and potholes.




Section 1



Section 2



Section 6



Section 6

Figure 7-8 Typical Sections of the Maniamba-Metangula road

7.8.2 Lichinga-Mandimba Road (N13)

This road connects Lichinga, the provincial capital, to Mandimba, and serves as the strategic route that connects Mandimba to the Malawi border. The terrain is winding and mountainous. The total length of the road is 148km. The road was constructed in 2007 as part of the short term interventions to minimise gravel loss on roads that were built under the 2005 emergency works programme. The construction comprises an Otta seal with a sand cover seal on a natural base and sub-base.

There are 10 study sections, with a combined length of 15km which form the surfaced sections that were built in 2007 as part of the short term interventions. The condition of the study sections range from good to very poor.

Details of the study sections are given in Table 7-10 and typical views of the sections are given in Figure 7-9.

Table 7-10 Characteristics of study sections

| | |
|--------------------|-------------------|
| PROVINCE | Niassa |
| Road Name | Lichinga Mandimba |
| Road Length | 148 km |

DATUM: Mandimba

| Section | Start Chainage | End Chainage | Section Length (km) | Surfacing Type | Base Materials | Visual Condition (Good, Fair, Poor) | Longitudinal Section Geometry (Flat, Slope, Rolling) | Cross-sectional Geometry (Trough, Crest, Flat) | Sub-surface drainage (Good, Fair, Poor) | Other Remarks |
|---------|----------------|--------------|---------------------|----------------|----------------|-------------------------------------|--|--|---|--|
| 1 | 0+000 | 0+900 | 0.9 | Otta seal | Natural Gravel | Very Poor | Flat | Flat | Good | Potholes mainly on centre line Cracking and patching Edge drops Road level below ground level |
| 2 | 0+900 | 2+700 | 1.8 | Otta seal | Natural Gravel | Good | Rolling | Flat | Good | Crocodile cracks on Mandimba bound lane Road level above ground level |
| 3 | 2+700 | 3+800 | 0.2 | Otta seal | Natural Gravel | Fair | Flat | Flat | Good | Potholes Rutting Road level at ground level |
| 4 | 3+800 | 4+900 | 1.1 | Otta seal | Natural Gravel | Fair | Slope | Flat | Good | Cracking Patching |
| | 9+500 | 10+800 | 1.3 | Otta seal | Natural Gravel | Poor | Rolling | Crest | Poor | Road level below ground level |
| 6 | 10+800 | 11+000 | 3.9 | Otta seal | Natural Gravel | Poor | Rolling | Crest | Poor | Road level above ground level |
| 7 | 11+000 | 13+300 | 2.3 | Otta seal | Natural Gravel | Poor | Rolling | Crest | Poor | Potholes on centre line of carriageway |
| 8 | 81+600 | 83+900 | 2.3 | Otta seal | Natural Gravel | Fair | Mountainous | Crest | Poor | Cracks, patches and potholes |
| 9 | 83+900 | 84+100 | 0.2 | Otta seal | Natural Gravel | Fair | Flat | Crest | Poor | Cracks, patches and potholes |
| 10 | 87+200 | 88+200 | 1 | Otta seal | Natural Gravel | Good | Low lying/sag | Crest | Poor | Cracks, patches and potholes |

Section 1 is 0.9km long and lies within the urban area of Mandimba. It is in a very poor condition characterised by edge drops, cracking, patching and potholes, the latter being localised within the middle of the carriageway. The road level lies below the ground level.

Section 2 is 1.8km long and is in a good condition. The road lies above ground level and there are some crocodile cracks on the Mandimba bound lane.



Section 1



Section 2



Section 8



Section 9

Figure 7-9 Typical sections of the Lichinga-Mandimba road

8 Recommendations

As described earlier in this report, nine candidate roads with representative ages, construction types, and conditions were selected for the reconnaissance survey. Study sections for each road were identified and details of the conditions were presented. The information is summarised in Table 8-1.

Table 8-1 Summary of road characteristics

| No | Road Name | Surfacing | Base | General Condition |
|----|-------------------------|-------------------------|-----------------------------|-------------------|
| 1 | Marracuene-Ferruviario | Sand seal | Emulsion Treated Base | Poor |
| 2 | Boane-Libombos | Double Surface Dressing | Granular and cement treated | Good to Poor |
| 3 | Pambara-Rio Save | Hot sand asphalt | Cement stabilised | Good |
| 4 | Rio Zambezi-Nicoadala | Hot sand asphalt | Cement stabilised | Good to Poor |
| 5 | Quelimane-Namacurra | Hot sand asphalt | Macadam | Good |
| 6 | Nametil-Angoche | Sand cover on Otta seal | Cement-stabilised | Good |
| 7 | Oasse-Mocimboa da Praia | Sand Seal | Emulsion Treated Base | Fair to Poor |
| 8 | Maniamba-Metangula | Sand cover on Otta seal | Natural gravel | Good to Poor |
| 9 | Mandimba-Lichinga | Sand cover on Otta seal | Natural gravel | Good to Poor |

In order to maximise the possible range of construction types in the detailed investigation phase of the project, to avoid unnecessary repetition, and to manage the project within the resources available, it is recommended that the following 7 roads, comprising 20 study sections be studied during the detailed phase (Table 8-2).

These roads were selected because they represent a broad range of surfacing type, condition, rainfall, traffic volume and age, and the 2 roads excluded from the sample (Marracuene - Ferruviario and Maniamba - Metangula) were found to have characteristics and construction types that were duplicated by other sections.

Table 8-2 Recommended roads and study sections

| No | Road Name | Age (yrs) | Surfacing | Base | General Condition | Inclusion in Detailed Investigation | Justification for Inclusion/Exclusion | No. of Sections |
|----|-------------------------|----------------|-------------------------|-----------------------|-------------------|-------------------------------------|--|-----------------|
| 1 | Marracuene-Ferruviario | 7 | Sand seal | Emulsion treated base | Poor | Exclude | Highly deteriorated and beyond analysis | N/A |
| 2 | Boane-Limbombos | No information | Double surface dressing | Granular | Good to Poor | Include | Only section with double Surface Dressing on Macadam base | 2 |
| | | | Double surface dressing | Cement stabilised | Good to Poor | Include | Only section with double Surface Dressing on cement treated sand base | 4 |
| 3 | Pambara-Rio Save | 3 | Hot sand asphalt | Cement stabilised | Good | Include | Sections generally in good condition throughout | 1 |
| 4 | Rio Zambezi-Nicoadala | No information | Hot sand asphalt | Cement stabilised | Good to Poor | Include | Sections showing more varied range of pavement condition compared to Pambara-Rio Save | 3 |
| 5 | Quelimane-Namacurra | No information | Hot sand asphalt | Crushed stone | Good | Include | Sections showing more varied range of pavement condition compared to Pambara-Rio Save | 1 |
| 6 | Nametil-Angoche | 5 | Sand cover on Otta seal | Cement stabilised | Good | Include | Only section with Otta seal on cement treated base | 3 |
| 7 | Oasse-Mocimboa da Praia | 11 | Sand Seal | Emulsion treated base | Fair to Poor | Include | Sections similar to Marracuene-Ferruviario and suitable for analysis | 3 |
| 8 | Maniamba-Metangula | 4 | Sand cover on Otta seal | Natural gravel | Good to Poor | Exclude | Section similar to Mandimba-Lichinga | N/A |
| 9 | Mandimba-Lichinga | 5 | Sand cover on Otta seal | Natural gravel | Good to Poor | Include | Section similar to Maniamba-Metangula but more varied in terms of terrain and road condition | 3 |

9 Programme for Detailed Investigations

In accordance with the Terms of Reference, the following activities will be carried out during the detailed investigation stages of each road:

9.1 Field Investigations

1. Visual condition assessments to measure and record the extent of cracking, patching, surface stripping and bleeding
2. Drainage evaluation to assess whether adequate surface and sub-surface drainage has been provided for and/or is functioning
3. Rut depth and roughness measurements using the Bump Integrator
4. Deflection tests to measure in-situ stiffness of the pavements – it has not been verified whether deflection data are available in ANE. If available and deemed to be sufficient, then deflection surveys will not be necessary.
5. DCP tests to determine the in-situ strength and layer thicknesses
6. Trial or test pit excavation to determine the profile of the pavement, to obtain in-situ dry density and moisture contents of the pavement layers and samples of the materials for laboratory testing of properties that cannot be obtained from non-destructive testing on site .
7. Extraction of cores of the surfacing for testing

9.2 Materials Testing

Classification: grading, Atterberg limits, linear shrinkage,

1. Compaction: MDD, OMC
2. In situ moisture content
3. Strength: CBR (soaked, OMC, 0.75 OMC)
4. Bituminous surfacing: binder content, aggregate characteristics.

Materials testing is critical to the successful completion of the project. It is important for the main stakeholders of the project to ensure that reliable results are obtained at this stage. Of particular concern is the testing of the bitumen. The assessment of the bitumen is expected to yield results which will influence the development of specifications for low volume roads. To this effect it is important to determine a number of parameters.

Bitumen becomes brittle with age, resulting in cracking and the ingress of water to the lower pavement layers causing a greatly increased rate of road deterioration. Although this cannot be prevented, the length of time that it takes for the bitumen to deteriorate to a critical level is vital for the overall performance of the road. Premature failure of surfacings is common nowadays and the causes could be the quality of the bitumen that is being supplied, flaws in the construction process or inappropriate surfacing choice or design which result in the too rapid alteration of the bitumen. Thus measuring the properties of both new and old bitumen is an essential component of the study.

Aging of fresh bitumen will help to determine how the bitumen change over time and this may reveal some deficiencies in performance in typical tropical environments

Ductility used to be a major test in the determination of bitumen quality and this has been eliminated over time and substituted with viscosity tests, which is an indirect test. Poor ductility in the binder leads to premature cracking of the surfacing such that crack initiation would take a much shorter period. Ductility tests will be carried out in this project in addition to the penetration and viscosity tests.

The plan is to carry out bitumen tests at TRL's laboratory in the UK using specialised equipment and expertise in the test procedures. The materials testing will be carried out in Mozambique and others in Zimbabwe Central Roads Laboratory.

The transportation of materials from the sites to the local laboratories will be the responsibility of ANE. Also materials testing in ANE laboratories will also be the responsibility of ANE with technical assistance rendered by TRL.

The capacity of the ANE provincial and headquarters and LEM to carry out the materials testing has been presented in Chapter 6 of this report.

9.3 Analysis and Documentation

A detailed technical review of existing data will be undertaken to establish its utility in carrying out the back analysis of the study sections. There is a possibility that some of the as-built and maintenance records may not be available for some of the study sections (for instance Boane-Limbombos-Goba, Oasse-Mocimboa da Praia and Rio Zambezi-Nicoadala). In such situations, the back analysis will be based solely on the results of the field investigations, laboratory testing, and local knowledge of ANE staff. This information will be complemented and compared with the HDM-4 deterioration models generated for the respective study sections.

The HDM-4 model will be used to generate deterioration models based on different scenarios of traffic loading, pavement type, environmental factors and maintenance regimes. The actual condition and performance of the study sections, evaluated using data collected from field surveys and laboratory testing, will be compared with the HDM-4 output, thereby making it possible to evaluate the performance trends of the study sections with respect to traffic, pavement type, material specifications and maintenance regimes.

The pavement deflection surveys data that were collected in 2011 was at 10km intervals and more strategic in its nature since the exercise was conducted to carry out a network level assessment. It is therefore very limited in its use for carrying out the back analysis, which requires data to be collected at shorter intervals.

Figure 9-1 on the next page shows the Activity Schedule, whilst

Table 9-1 shows a list of the bitumen, deflection and other associated tests that are required to fully assess the performance of the pavements and their material characteristics.

Figure 9-1 Activity Schedule




Table 9-1 Materials required to assess performance

| Item | | Test Method | Estimated no. of samples | Remarks |
|------|---|--------------|--------------------------|--|
| | Soil and Pavement Materials Tests | | | 2 test pits for Pambarra-Rio Save and 1 pit per section for all other study sections |
| 1 | Plastic Limit | BS 1377-2 | 63 | 3 samples/pit (base, subbase and subgrade) |
| 2 | Liquid Limit | BS 1377-2 | 63 | 3 samples/pit (base, subbase and subgrade) |
| 3 | Shrinkage Limit | BS 1377-2 | 63 | 3 samples/pit (base, subbase and subgrade) |
| 4 | Dry Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | BS EN 933-1 | 42 | 2 samples/pit (base, subbase and subgrade) |
| 5 | Wet Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | BS 1377-7 | 42 | 2 samples/pit (base, subbase and subgrade) |
| 6 | Moisture Content Determination (Oven drying 105-110°C) | BS 1377-7 | 63 | 3 samples/pit (base, subbase and subgrade) |
| 7 | Maximum Dry Density Determination (MDD) | BS 1377-7 | 42 | 2 samples/pit (base, subbase and subgrade) |
| 8 | California Bearing Ratio (CBR) | EN 13286-47 | 63 | 3 samples/pit (base, subbase and subgrade) |
| 9 | Triaxial Tests | BS 1377-8 | 21 | 1 samples/pit (base, subbase and subgrade) |
| 10 | In Situ Density by Sand Replacement Method | BS EN 12390 | 42 | 2 samples/pit (base, subbase and subgrade) |
| | Aggregate and Surfacing Materials Tests | | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |
| 11 | Aggregate Crushing Value (ACV) - Dry Test | BS EN 1097-2 | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |
| 12 | Aggregate Crushing Value (ACV) - Wet Test | BS EN 1097-2 | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |

Inception Report

| | | | | |
|----|--|--------------|----|---|
| 13 | 10% Fines Aggregate Crushing Test (10%FACT) - Dry Test | BS EN 1097-2 | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |
| 14 | 10% Fines Aggregate Crushing Test (10%FACT) - Wet Test | BS EN 1097-2 | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |
| 15 | Aggregate Impact Value (AIV) - Dry | BS EN 1097-2 | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |
| 16 | Aggregate Impact Value (AIV) - Wet | BS EN 1097-2 | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |
| 17 | Water Absorption | BS EN 13755 | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |
| 18 | Flakiness Index Test | BS EN 933-3 | 9 | 3 samples for each road (Boanne-Limbombos, Nametil-Angoche and Lichinga Mandimba) |
| | Bitumen Tests | | | |
| 19 | Bitumen Extraction Test (Composition) | EN 12697-1 | 30 | For 6 roads and 5 sections per road, 1 sample per section. |
| 20 | Bitumen Recovery | EN 12697-3 | 12 | For 6 roads two samples recovered for the tests below. That is 12 samples. |
| 21 | Rolling Thin Film Oven Test (RTFOT) | EN 12607-1 | 18 | Ageing 3 samples for each of 2 cut-backs, 2 pengrades and 2 emulsions |
| 22 | Softening Point Test | EN 12697-1 | 10 | Samples recovered from 2 above plus 2 samples of emulsion and 2 samples of penetration |
| 23 | Penetration Test | EN 1426 | 10 | Samples recovered from 2 above plus 2 samples of emulsion and 2 samples of penetration |
| 24 | Standard Viscosity Test (STV) | EN 1427 | 4 | 2 samples of cut-back and 2 samples of prime. |
| 25 | Ductility Tests | EN 13589 | 18 | Fresh samples of 2 cut-backs, 2 pengrades and 2 emulsions and repeated on un-aged samples and repeated on 6 recovered samples |
| 26 | Analytical Test Method: Composition | BS598-102 | 8 | Samples of 2 cut-backs, 2 pengrades and 2 emulsions and 2 primes. |

10 References

1. TRL (2006). Engineering Standards and Life Cycle Costing for Low-Volume Labour Based and Unpaved Roads – Mozambique Country Component: Final Report. Crowthorne: TRL Limited
2. Mukura, K. (2006). Guideline for Quality Assurance Procedures for Road Works. Crowthorne: TRL Limited
3. Overby, C. (1999). A Guide to the Use of Otta Seals. Oslo: Directorate of Public Roads, Road Technology Department International Division
4. ANE (2007). Normas de Execucao (Work Norms). Maputo: National Roads Administration
5. Ministry of Transport and Energy, Department of Roads, Part P Materials Specifications Manual
6. Ministry of Transport and Energy, Department of Roads, Part F Construction Manual
7. TRL (2006). SADC Guideline: Low Volume Sealed Roads. Southern Africa Development Community (SADC)

Appendix A - Assessment of laboratory capacity

Province
Number of staff

Cabo Delgado
4

| Tests | Equipment Available to perform? | Staff Available to perform? | Remarks |
|---|--|------------------------------------|---------------------------|
| Soil and Pavement Materials Tests | | | |
| Plastic Limit | Yes | Yes | |
| Liquid Limit | Yes | Yes | |
| Shrinkage Limit | Yes | Yes | |
| Dry Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Wet Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Moisture Content Determination (Oven drying 105-110°C) | Yes | Yes | |
| Maximum Dry Density Determination (MDD) | Yes | Yes | |
| California Bearing Ratio (CBR) | Yes | Yes | |
| Triaxial Tests | No | No | |
| In Situ Density by Sand Replacement Method | Yes | Yes | |
| In Situ Density by Nuclear Gauge | No | Yes | |
| Aggregate and Surfacing Materials Tests | | | |
| Aggregate Crushing Value (ACV) - Dry Test | Yes | Yes | Machine needs calibration |
| Aggregate Crushing Value (ACV) - Wet Test | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) | Yes | Yes | |
| Aggregate Impact Value (AIV) - Dry | Yes | Yes | |
| Aggregate Impact Value (AIV) - Wet | Yes | Yes | |
| Los Angeles Abrasion Value (LAV) | No | No | |
| Water Absorption | Yes | Yes | |
| Flakiness Index Test | Yes | Yes | |
| Bitumen Tests | | | |
| Bitumen Affinity | No | No | |
| Softening Point Test | No | No | |
| Penetration Test | No | No | |
| Distillation (Composition Tests) | No | No | |
| Ductility Tests | No | No | |

Inception Report

Province
Number of staff

Inhambane
4

| | Equipment Available to perform? | Staff Available to perform? | Remarks |
|---|--|------------------------------------|--|
| Tests | | | |
| Soil and Pavement Materials Tests | | | |
| Plastic Limit | Yes | Yes | |
| Liquid Limit | Yes | Yes | |
| Shrinkage Limit | Yes | Yes | |
| Dry Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Wet Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Moisture Content Determination (Oven drying 105-110°C) | Yes | Yes | |
| Maximum Dry Density Determination (MDD) | Yes | Yes | |
| California Bearing Ratio (CBR) | Yes | Yes | |
| Triaxial Tests | No | No | |
| In Situ Density by Sand Replacement Method | Yes | Yes | |
| In Situ Density by Nuclear Gauge | No | Yes | Equipment for ongoing project use only |
| Aggregate and Surfacing Materials Tests | | | |
| Aggregate Crushing Value (ACV) - Dry Test | Yes | Yes | |
| Aggregate Crushing Value (ACV) - Wet Test | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) - Dry | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) - Wet | Yes | Yes | |
| Aggregate Impact Value (AIV) - Dry | Yes | Yes | |
| Aggregate Impact Value (AIV) - Wet | Yes | Yes | |
| Los Angeles Abrasion Value (LAV) | No | No | |
| Water Absorption | Yes | Yes | |
| Flakiness Index Test | Yes | Yes | |
| Bitumen Tests | | | |
| Bitumen Affinity | No | No | |
| Softening Point Test | No | No | |
| Penetration Test | No | No | |
| Distillation (Composition Tests) | No | No | |
| Ductility Tests | No | No | |

Inception Report

Province Maputo
Number of staff 3

| Tests | Equipment Available to perform? | Staff Available to perform? | Remarks |
|---|---------------------------------|-----------------------------|---------|
| Soil and Pavement Materials Tests | | | |
| Plastic Limit | Yes | Yes | |
| Liquid Limit | Yes | Yes | |
| Shrinkage Limit | Yes | Yes | |
| Dry Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Wet Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Moisture Content Determination (Oven drying 105-110°C) | Yes | Yes | |
| Maximum Dry Density Determination (MDD) | Yes | Yes | |
| California Bearing Ratio (CBR) | Yes | Yes | |
| Triaxial Tests | No | No | |
| In Situ Density by Sand Replacement Method | No | Yes | |
| Aggregate and Surfacing Materials Tests | | | |
| Aggregate Crushing Value (ACV) - Dry Test | Yes | Yes | |
| Aggregate Crushing Value (ACV) - Wet Test | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) | Yes | Yes | |
| Aggregate Impact Value (AIV) - Dry | Yes | Yes | |
| Aggregate Impact Value (AIV) - Wet | Yes | Yes | |
| Los Angeles Abrasion Value (LAV) | No | No | |
| Water Absorption | Yes | Yes | |
| Flakiness Index Test | Yes | Yes | |
| Bitumen Tests | | | |
| Bitumen Affinity | No | No | |
| Softening Point Test | No | No | |
| Penetration Test | No | No | |
| Distillation (Composition Tests) | No | No | |
| Ductility Tests | No | No | |

Inception Report

Province
Number of staff

Nampula
3

| Tests | Equipment Available to perform? | Staff Available to perform? | Remarks |
|---|---------------------------------|-----------------------------|---------|
| Soil and Pavement Materials Tests | | | |
| Plastic Limit | Yes | Yes | |
| Liquid Limit | Yes | Yes | |
| Shrinkage Limit | Yes | Yes | |
| Dry Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Wet Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Moisture Content Determination (Oven drying 105-110°C) | Yes | Yes | |
| Maximum Dry Density Determination (MDD) | Yes | Yes | |
| California Bearing Ratio (CBR) | Yes | Yes | |
| Triaxial Tests | No | No | |
| In Situ Density by Sand Replacement Method | Yes | Yes | |
| Aggregate and Surfacing Materials Tests | | | |
| Aggregate Crushing Value (ACV) - Dry Test | Yes | Yes | |
| Aggregate Crushing Value (ACV) - Wet Test | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) - Dry Test | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) - Wet Test | Yes | Yes | |
| Aggregate Impact Value (AIV) - Dry | Yes | Yes | |
| Aggregate Impact Value (AIV) - Wet | Yes | Yes | |
| Los Angeles Abrasion Value (LAV) | No | No | |
| Water Absorption | Yes | Yes | |
| Flakiness Index Test | Yes | Yes | |
| Bitumen Tests | | | |
| Bitumen Affinity | No | No | |
| Softening Point Test | No | No | |
| Penetration Test | No | No | |
| Distillation (Composition Tests) | No | No | |
| Ductility Tests | No | No | |

Inception Report

Province
Number of staff

Niassa
1

| Tests | Equipment Available to perform? | Staff Available to perform? | Remarks |
|---|---------------------------------|-----------------------------|--|
| Soil and Pavement Materials Tests | | | Only 1 laboratory staff available for the whole province |
| Plastic Limit | Yes | No | |
| Liquid Limit | Yes | No | |
| Shrinkage Limit | Yes | No | |
| Dry Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | No | |
| Wet Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | No | |
| Moisture Content Determination (Oven drying 105-110°C) | Yes | No | |
| Maximum Dry Density Determination (MDD) | Yes | No | |
| California Bearing Ratio (CBR) | No | No | Machine needs calibration |
| Triaxial Tests | No | No | |
| In Situ Density by Sand Replacement Method | Yes | No | |
| In Situ Density by Nuclear Gauge | Yes | No | 3 machines available |
| | | | |
| Aggregate and Surfacing Materials Tests | | | Machine broken down |
| Aggregate Crushing Value (ACV) - Dry Test | No | No | |
| Aggregate Crushing Value (ACV) - Wet Test | No | No | |
| 10% Fines Aggregate Crushing Test (10%FACT) - Dry Test | No | No | |
| 10% Fines Aggregate Crushing Test (10%FACT) - Wet Test | No | No | |
| Aggregate Impact Value (AIV) - Dry | No | No | |
| Aggregate Impact Value (AIV) - Wet | No | No | |
| Los Angeles Abrasion Value (LAV) | No | No | |
| Water Absorption | No | No | |
| Flakiness Index Test | No | No | |
| | | | |
| Bitumen Tests | | | |
| Bitumen Affinity | No | No | |
| Softening Point Test | No | No | |
| Penetration Test | No | No | |
| Distillation (Composition Tests) | No | No | |
| Ductility Tests | No | No | |

Inception Report

Province
Number of staff

Zambezia
3

| Tests | Equipment Available to perform? | Staff Available to perform? | Remarks |
|---|---------------------------------|-----------------------------|---------------------|
| Soil and Pavement Materials Tests | | | |
| Plastic Limit | Yes | Yes | |
| Liquid Limit | Yes | Yes | |
| Shrinkage Limit | Yes | Yes | |
| Dry Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Wet Sieve Analysis (All BS Sieves from 50mm down to 75µm(No.200)) | Yes | Yes | |
| Moisture Content Determination (Oven drying 105-110°C) | Yes | Yes | |
| Maximum Dry Density Determination (MDD) | Yes | Yes | |
| California Bearing Ratio (CBR) | Yes | Yes | |
| Triaxial Tests | No | No | |
| In Situ Density by Sand Replacement Method | Yes | | |
| In Situ Density by Nuclear Gauge | No | | Troxler not working |
| Aggregate and Surfacing Materials Tests | | | |
| Aggregate Crushing Value (ACV) - Dry Test | Yes | Yes | |
| Aggregate Crushing Value (ACV) - Wet Test | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) - Dry Test | Yes | Yes | |
| 10% Fines Aggregate Crushing Test (10%FACT) - Wet Test | Yes | Yes | |
| Aggregate Impact Value (AIV) - Dry | No | | |
| Aggregate Impact Value (AIV) - Wet | No | | |
| Los Angeles Abrasion Value (LAV) | No | | |
| Water Absorption | Yes | | |
| Flakiness Index Test | Yes | | |
| Bitumen Tests | | | |
| Bitumen Affinity | No | | |
| Softening Point Test | No | | |
| Penetration Test | No | | |
| Distillation (Composition Tests) | No | | |
| Ductility Tests | No | | |

| Capacity of ANE and LEM laboratories to carry out materials testing | | | | | | |
|--|---|--------------------|---|--|---|---|
| Additional Tests | | | | | | |
| Item | | Test Method | Estimated number of samples to be tested | Does ANE have Equipment and personel to do the test | If NO, does the National Laboratory have capacity to carry out | Remarks |
| | Bitumen Tests | | | Yes/No | Yes/No | |
| 1 | Bitumen Extraction Test (Composition) | EN 12697-1 | 30 | NO | NO | For 6 roads and 5 sections per road, 1 sample per section. |
| 2 | Bitumen Recovery | EN 12697-3 | 12 | NO | NO | For 6 roads two samples recovered for the tests below. That is 12 samples. |
| 3 | Rolling Thin Film Oven Test (RTFOT) | EN 12607-1 | 18 | NO | NO | Ageing 3 samples for each of 2 cut-backs, 2 pengrades and 2 emulsions |
| 4 | Softening Point Test | EN 12697-1 | 10 | NO | NO | Samples recovered from 2 above plus 2 samples of emulsion and 2 samples of penetration |
| 5 | Penetration Test | EN 1426 | 10 | NO | YES | Samples recovered from 2 above plus 2 samples of emulsion and 2 samples of penetration |
| 6 | Standard Viscosity Test (STV) | EN 1427 | 4 | NO | NO | 2 samples of cut-back and 2 samples of prime. |
| 7 | Distillation (Composition Tests) | EN 1431 | 4 | NO | NO | 2 samples of cut-back and 2 samples of prime. |
| 8 | Ductility Tests | EN 13589 | 18 | NO | NO | From aged samples of 2 cut-backs, 2 pengrades and 2 emulsions and repeated on un-aged samples and repeated on 6 recovered samples |
| 9 | DSR Method: Complex Shear Modulus and Phase Angle | EN 14770 | 18 | NO | NO | From aged samples of 2 cut-backs, 2 pengrades and 2 emulsions and repeated on un-aged samples and repeated on 6 recovered samples |
| 10 | Analytical Test Method: Composition | BS598-102 | 8 | NO | NO | samples of 2 cut-backs, 2 pengrades and 2 emulsions and 2 primes. |
| 11 | Storage stability of modified bitumen | EN 13399 | 6 | NO | NO | For 2 emulsion samples and 2 cutbacks and 2 pengrades |

| Capacity of ANE and LEM laboratories to carry out materials testing | | | | | | |
|--|---|--------------------|---|---|--|---|
| Additional Tests | | | | | | |
| Item | | Test Method | Estimated number of samples to be tested | Does ANE have Equipment and personel to do the test Yes/No | If NO, does the National Laboratory have capacity to carry out Yes/No | Remarks |
| | Bitumen Tests | | | | | |
| | Soil and Pavement Materials Tests | | | | | |
| | Triaxial Tests (U100 quick undrained or multistage) | BS 1377 Part 7 | 18 | NO | NO | 12 base material samples from 6 roads and 6 samples from 6 borrow pits |
| | Aggregate and Surfacing Materials Tests | | | | | |
| | Polished Stone Value (PSV) | EN 1097-8 | 6 | NO | NO | 6 surface agregate samples from 6 roads. |
| | Petrography (Mineralogy) | EN 932-3 | 12 | NO | NO | 6 Surface agregate samples from 6 roads and six base samples from 6 roads |
| | In-Situ Tests | | | | | |
| | | | | | | |

Appendix B – Cyclones Data

| Nome de Tempesta de | Duração | Intensidade | Classificação | Local Afectado |
|----------------------------|---------------------|------------------------------------|--|--------------------------------------|
| Astride | 23/12/99 – 03/01/00 | 95km/h (60mph) 985 hPa (mbar) | Tempestade Tropical Severa Categoria I | Mongincual |
| Leon-Eline | 07/02-22/02/00 | 185km/h (115mph) 930 hPa (mbar) | Ciclone Tropical Intenso Categoria IV | Maputo e Gaza |
| Hudah | 24/03-08/04/00 | 220km/h (140mph) 905 hPa (mbar) | Ciclone Tropical Categoria IV | Zambézia e Nampula |
| Dera | 05/03-12/03/01 | 140km/h (85mph) 960 hPa (mbar) | Ciclone Tropical Categoria II | Zambézia e Nampula |
| Cyprien | 30/12/01-03/01/02 | 100km/h (65mph) 980 hPa (mbar) | Tempestade Tropical Severa | Costa de Sofala e Zambezia |
| Atang | 04-12/11/2002 | 55km/h (35mph) 998 hPa (mbar) | Tempestade Tropical | Costa de Cabo Delgado |
| Delfina | 30/12/02-05/01/03 | 90km/h (55mph) 984 hPa (mbar) | Tempestade Tropical Severa | Nampula e Norte da Zambézia |
| Japhet | 25/2-06/03/2003 | 112km/h (70mph) | Ciclone Tropical Intenso Categoria IV | Inhambane, Manica e sul de Sofala |
| Cela | 05-21/12/2003 | 120km/h (75mph) 975 hPa (mbar) | Ciclone Tropical Categoria I | Canal de Moçambique |
| Elita | 26/01-12/02/2004 | 120km/h (75mph) 970 hPa (mbar) | Ciclone Tropical Categoria I | Canal de Moçambique |

| | | | | |
|-----------------|-------------------|------------------------------------|---|-----------------------------|
| Gafilo | 01/03-01/03/2004 | 230km/h (145mph) 895 hPa (mbar) | Ciclone Tropical Muito Intenso Categoria V | Costa de Inhambane e Sofala |
| Ernest | 16/01-25/01/05 | 165km/h (105mph) 950 hPa (mbar) | Ciclone Tropical Intenso Categoria III | Costa de Sofala e Zambezia |
| Boloetse | 20/01/05-06/02/06 | 155km/h (100mph) 950 hPa (mbar) | Ciclone Tropical Intenso Categoria III | Zambezia |
| Anita | 26/11/05-04/12/06 | 83km/h (52mph) 996 hPa (mbar) | Tempestade Tropical Moderada | Canal de Moçambique |
| Favio | 11/02-23/02/2007 | 222km/h (138mph) 925 hPa (mbar) | Ciclone Tropical Intenso Categoria IV | Inhambane e Vilanculos |
| Jaya | 26/03-08/04/07 | 222km/h (138mph) 935 hPa (mbar) | Ciclone Tropical Intenso Categoria III | Costa norte de Moçambique |
| Elnus | 29/12/07-05/01/08 | 65km/h (40mph) 995 hPa (mbar) | Tempestade Tropical Moderada | Canal de Moçambique |
| Jokwe | 02/03-16/03/2008 | 195km/h (120mph) 940 hPa (mbar) | Ciclone Tropical Intenso Categoria III | Nampula e Zambézia |
| Fanel | 18/01-23/01/09 | 185km/h (115mph) 927 hPa (mbar) | Ciclone Tropical Intenso Categoria III | Canal de Moçambique |
| Izilda | 24/03-27/03/09 | 200km/h (175mph) 978 hPa (mbar) | Tempestade Tropical Severa Categoria I | Canal de Moçambique |
| Joel | 26/05-29/05/10 | 111km/h (69mph) 996 hPa (mbar) | Depressao Tropical | Canal de Moçambique |

Appendix C – Rainfall Data

Estação: Marracuene

Período: 1997 - 2011

Elemento: Precipitação total mensal (das 9 as 9 horas em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|------|-------|-------|------|------|-------|-------|-------|
| 1996 | 192.3 | 232.3 | 228.2 | 37.9 | 7.3 | 6.3 | 154.8 | 0.0 | 7.5 | 110.7 | 90.3 | 39.9 |
| 1997 | 219.4 | 326.5 | 40.8 | 27.6 | 28.2 | 0.6 | 84.0 | 42.3 | 26.5 | 90.3 | 176.2 | 40.3 |
| 1998 | 156.5 | 62.5 | 52.0 | 83.9 | 24.3 | 19.3 | 1.4 | 5.8 | 7.1 | 34.5 | 205.8 | 90.8 |
| 1999 | 277.7 | 273.1 | 154.2 | 115.5 | 39.7 | 20.3 | 12.0 | 17.0 | 65.9 | 39.4 | 138.0 | 38.0 |
| 2000 | 193.0 | 490.0 | 335.1 | 102.2 | 23.0 | 33.2 | 35.0 | 0.5 | 18.2 | 40.5 | 202.6 | 95.9 |
| 2001 | 35.2 | 258.6 | 104.1 | 93.7 | 0.0 | 20.5 | 22.8 | 1.2 | 5.0 | 43.0 | 199.4 | 208.1 |
| 2002 | 156.2 | 16.2 | 44.2 | 5.0 | 0.0 | 11.7 | 76.0 | 2.5 | 6.5 | 82.9 | 35.5 | 76.2 |
| 2003 | 25.5 | 80.7 | 133.9 | 31.7 | 17.6 | 123.7 | 12.2 | 0.0 | 44.5 | 22.0 | 5.1 | 34.5 |
| 2004 | 158.2 | 177.0 | 238.4 | 67.0 | 7.2 | 14.5 | 33.2 | 8.3 | 17.5 | 89.7 | 76.1 | 85.6 |
| 2005 | 136.6 | 70.9 | 118.0 | 45.5 | 60.5 | 2.5 | 7.5 | 0.0 | 3.7 | 12.0 | 134.5 | 115.7 |
| 2006 | 24.2 | 29.3 | 22.0 | 6.3 | 31.7 | 20.5 | 0.0 | 0.0 | -- | 10.7 | 68.4 | -- |
| 2007 | 148.0 | 157.1 | 333.5 | 35.5 | 21.3 | 7.5 | 22.3 | 30.9 | 2.0 | 146.7 | 22.3 | 99.0 |
| 2008 | 91.4 | 39.0 | 82.4 | 51.1 | 8.0 | 0.0 | 5.5 | 7.0 | 18.5 | 195.0 | -- | 36.8 |
| 2009 | 47.0 | 44.5 | 48.0 | 17.5 | 43.1 | 0.0 | 0.0 | 26.0 | 0.0 | 5.5 | 14.3 | 162.2 |
| 2010 | 231.0 | 39.6 | 26.5 | 70.3 | 33.7 | 22.5 | 3.5 | 19.0 | 0.0 | 0.0 | 4.9 | 33.5 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Estação: Umbeluzi

Elemento: Precipitação total mensal (das 9 as 9 horas em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|------|------|-------|------|------|-------|-------|-------|
| 1997 | 73.6 | 109.0 | 64.0 | 55.7 | 7.5 | 25.6 | 137.0 | 0.3 | 0.0 | 81.8 | 8.3 | 93.5 |
| 1998 | 217.0 | 81.0 | 22.6 | 50.4 | 5.0 | 15.0 | 0.0 | 12.5 | 2.0 | 74.5 | 63.5 | 113.8 |
| 1999 | 53.5 | 89.3 | 99.2 | 53.1 | 3.8 | 32.2 | 11.5 | 82.1 | 89.1 | 58.5 | 80.1 | 21.5 |
| 2000 | 531.2 | 114.3 | 8.5 | 60.7 | 6.0 | 42.2 | 0.0 | 19.1 | 23.1 | 16.9 | 50.2 | 72.6 |
| 2001 | 112.6 | 204.2 | 23.2 | 31.8 | 9.4 | 0.0 | 14.5 | 6.6 | 4.3 | 19.6 | 316.4 | 158.2 |
| 2002 | 65.5 | 17.5 | 17.0 | 2.5 | 0.0 | 0.0 | 15.4 | 9.2 | 30.8 | 45.3 | 14.1 | 47.6 |
| 2003 | 5.8 | 74.2 | 28.6 | 2.0 | 9.1 | 57.6 | 5.2 | 0.0 | 28.8 | 6.6 | 17.9 | 20.2 |
| 2004 | 189.7 | 75.0 | 89.0 | 36.0 | 8.9 | 2.9 | 76.0 | 18.0 | 1.7 | 42.2 | 108.7 | 56.6 |
| 2005 | 162.2 | 48.9 | 111.2 | 35.8 | 9.2 | 1.1 | 1.2 | 7.2 | 23.1 | 8.6 | 34.1 | 16.9 |
| 2006 | 98.3 | 97.5 | 163.7 | 22.7 | 1.5 | 3.6 | 8.3 | 18.8 | 11.6 | 43.0 | 104.4 | 118.7 |
| 2007 | 24.2 | 64.8 | 43.0 | 118.0 | 0.0 | 5.1 | 7.9 | 0.0 | 13.3 | 39.7 | 51.7 | 210.3 |
| 2008 | 77.0 | 31.0 | 85.2 | 48.7 | 15.2 | 14.2 | 0.0 | 0.0 | 15.2 | 0.5 | 0.0 | 23.6 |
| 2009 | 129.9 | 72.4 | 76.3 | 5.4 | 1.7 | 28.5 | 13.7 | 8.3 | 14.6 | 0.0 | 26.2 | 94.3 |
| 2010 | 32.8 | 125.2 | 100.7 | 22.0 | 25.2 | 14.2 | 0.6 | 8.5 | | 118.5 | 129.9 | 246.6 |
| 2011 | 121.2 | 32.0 | 62.5 | 12.5 | 0.0 | 0.0 | 0.0 | 25.0 | 0.0 | 60.9 | 120.7 | 135.8 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Vilanculos

Elemento: Precipitação total mensal (das 9 as 9 horas em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|------|-------|------|------|------|-------|-------|-------|
| 1997 | 290.1 | 72.0 | 87.5 | 43.2 | 16.0 | 12.1 | 63.9 | 1.6 | 24.8 | 113.2 | 127.9 | 12.4 |
| 1998 | 263.2 | 54.7 | 158.2 | 57.3 | 24.6 | 0.9 | 10.3 | 32.6 | 23.0 | 51.1 | 94.0 | 327.2 |
| 1999 | 396.0 | 914.5 | 180.7 | 20.5 | 40.1 | 42.8 | 24.9 | 14.7 | 0.2 | 11.8 | 49.1 | 108.3 |
| 2000 | 51.9 | 546.9 | 361.7 | 100.9 | 57.1 | 39.6 | 62.3 | 24.4 | 5.2 | 2.5 | 101.1 | 236.0 |
| 2001 | 90.5 | 545.4 | 370.8 | 88.0 | 24.3 | 43.1 | 21.5 | 3.6 | 4.2 | 8.5 | 122.5 | 224.2 |
| 2002 | 11.9 | 9.1 | 84.3 | 28.6 | 2.4 | 33.7 | 70.8 | 17.6 | 18.7 | 46.3 | 73.4 | 5.3 |
| 2003 | 41.6 | 38.5 | 221.5 | 26.4 | 16.5 | 199.7 | 4.6 | 1.2 | 23.3 | 70.9 | 42.3 | 2.4 |
| 2004 | 62.6 | 72.9 | 191.3 | 65.4 | 29.8 | 20.0 | 5.6 | 0.7 | 5.3 | 106.6 | 9.8 | 121.2 |
| 2005 | 50.7 | 44.1 | 86.1 | 13.3 | 27.2 | 8.4 | 18.9 | 0.7 | 19.7 | 3.0 | 25.4 | 482.0 |
| 2006 | 65.1 | 139.9 | 447.1 | 82.2 | 39.4 | 83.2 | 5.8 | 8.8 | 0.0 | 0.0 | 3.7 | 42.8 |
| 2007 | 241.4 | 193.4 | 217.7 | 76.8 | 7.5 | 51.9 | 11.0 | 3.2 | 1.3 | 4.0 | 95.7 | 129.4 |
| 2008 | 121.2 | 64.9 | 122.0 | 14.8 | 88.0 | 281.0 | 9.7 | 2.7 | 6.7 | 0.6 | 12.3 | 277.3 |
| 2009 | 253.0 | 168.6 | 117.7 | 48.5 | 50.2 | 25.5 | 31.8 | 8.0 | 6.1 | 6.5 | 165.3 | 31.4 |
| 2010 | 137.7 | 162.0 | 128.0 | 153.4 | 31.3 | 16.8 | 75.3 | 4.7 | 0.0 | 0.8 | 37.4 | 96.5 |
| 2011 | 208.4 | 15.3 | 10.0 | 124.8 | 19.0 | 50.3 | 31.6 | 0.2 | 1.2 | 26.8 | 20.9 | 35.5 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Caia

Elemento: Precipitação total mensal (das 9 as 9 horas, em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|------|------|------|------|------|------|-------|-------|
| 1997 | 105.6 | 66.6 | 109.3 | 184.9 | 83.8 | 11.4 | 8.9 | 42.2 | 34.2 | 43.1 | 215.1 | 120.2 |
| 1998 | 282 | 38.6 | 124.1 | 46.4 | 70.5 | 21.2 | 0.0 | 2.5 | 1 | 0.0 | 6.5 | 176 |
| 1999 | 270.6 | 217.4 | 48.7 | 46.5 | 10 | 17.3 | 35.4 | 49.2 | 77.8 | 25 | 47.3 | 166.8 |
| 2000 | 142.7 | 47.2 | 11.8 | 41.6 | 51.1 | 4.8 | 0.0 | 12.2 | 49.2 | 36.6 | 225.1 | 284.8 |
| 2001 | 103.2 | 82.1 | 33.8 | 50.0 | 12.5 | 21.2 | 20.6 | 7.0 | 3.7 | 23.6 | 91.8 | 92.8 |
| 2002 | 252.2 | 116.3 | 102.0 | 174.0 | 51.7 | 53.6 | 58.6 | 2.6 | 1.4 | 2.9 | 31.4 | 256.4 |
| 2003 | 89.7 | 177.7 | 211.3 | 134.0 | 71.7 | 63.6 | 62.5 | 13.4 | 21.1 | 15.0 | 66.8 | 104.4 |
| 2004 | 87.7 | 164.9 | 84.3 | 27.1 | 8.9 | 49.5 | 27.7 | 4.8 | 0.0 | 18.1 | 62.4 | 63.1 |
| 2005 | 175.2 | 373.9 | 247.3 | 118.1 | 68.3 | 32.5 | 8.6 | 0.0 | 5.2 | 5.8 | 43.8 | 253.2 |
| 2006 | 248.6 | 91.1 | 117.5 | 19.4 | 0.0 | 29 | 54.5 | 24.7 | 8.5 | 18.5 | 66 | 81.5 |
| 2007 | 333.1 | 307.9 | 185.3 | 61.3 | 9.2 | 43.7 | 42.0 | 0.0 | 0.0 | 69 | 0.0 | 118.2 |
| 2008 | 202.8 | 86.7 | 167.7 | 22.8 | 2.5 | 29.5 | 25.1 | 14.3 | 0.2 | 63.8 | 8.9 | 155.9 |
| 2009 | 96.9 | 189 | 441.3 | 138.3 | 34.4 | 29 | 68 | 5.3 | 14.1 | 0.0 | 57.7 | 300.5 |
| 2010 | 78.3 | 183.6 | 59.6 | 42.9 | 50.4 | 12.5 | 23.0 | 10.0 | 0.0 | 0.6 | 112.3 | 109.2 |
| 2011 | 50.0 | 21.8 | 54.5 | 18.6 | 7.1 | 18.4 | 25.4 | 8.9 | 2.5 | 13.3 | 45.7 | 57.7 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Quelimane

Elemento: Precipitação total mensal (das 9 as 9 horas, em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|-------|-------|-------|-------|------|------|-------|-------|
| 1997 | 156.5 | 576.0 | 117.9 | 94.6 | 34.8 | 2.4 | 91.7 | 17.5 | 40.7 | 32.3 | 116.9 | 213.7 |
| 1998 | 463.8 | 267.6 | 155.3 | 53.2 | 26.4 | 20.6 | 54.0 | 106.5 | 11.4 | 67.0 | 71.0 | 114.8 |
| 1999 | 294.4 | 212.0 | 185.1 | 365.6 | 43.0 | 37.5 | 112.3 | 8.3 | 5.1 | 21.4 | 59.7 | 122.8 |
| 2000 | 436.6 | 170.7 | -- | 261.5 | 126.9 | 63.2 | 169.1 | 25.7 | 13.9 | 18.0 | 96.0 | 209.3 |
| 2001 | 600.8 | 316.8 | 395.2 | 54.0 | 118.5 | 1.7 | 55.7 | 18.4 | 5.1 | 1.0 | 6.7 | 139.4 |
| 2002 | 220.1 | 253.1 | 172.4 | 16.3 | 18.6 | 78.7 | 6.0 | 36.4 | 18.5 | 41.2 | 10.7 | 63.4 |
| 2003 | 387.3 | 256.0 | 326.7 | 67.9 | 38.8 | 94.2 | 50.9 | 14.6 | 12.6 | 0.3 | 35.0 | 143.7 |
| 2004 | 166.6 | 189.9 | 101.7 | 156.1 | 155.2 | 137.9 | 34.3 | 9.5 | 42.1 | 4.7 | 59.5 | 129.1 |
| 2005 | 145.3 | 205.1 | 300.7 | 53.6 | 62.9 | 34.0 | 29.3 | 2.3 | 20.4 | 2.9 | 1.6 | 264.0 |
| 2006 | 165.1 | 81.7 | 193.0 | 132.7 | 103.2 | 62.7 | 7.8 | 1.0 | 34.5 | 14.7 | 92.2 | 139.4 |
| 2007 | 639.5 | 150.8 | 211.9 | 161.1 | 77.6 | 24.3 | 58.6 | 12.1 | 0.0 | 3.6 | 195.2 | 262.5 |
| 2008 | 249.1 | 144.9 | 170.0 | 27.2 | 39.4 | 33.0 | 18.6 | 34.6 | 5.3 | 0.3 | 2.6 | 140.7 |
| 2009 | 109.1 | 209.5 | 241.4 | 111.2 | 32.7 | 5.9 | 67.5 | 26.0 | 1.9 | 14.5 | 18.3 | 145.0 |
| 2010 | 85.9 | 174.2 | 105.4 | 88.6 | 44.5 | 118.5 | 70.8 | 17.5 | 0.8 | 1.5 | 32.6 | 219.6 |
| 2011 | 174.3 | 296.3 | 247.8 | 237.9 | 48.3 | 12.8 | 107.9 | 48.6 | 9.9 | 26.5 | 32.3 | 97.3 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Namacurra

Elemento: Precipitação total mensal (das 9 às 9h, em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|------|-------|-------|------|------|------|-------|-------|
| 1995 | 419.0 | 349.2 | 155.5 | 75.6 | 11.3 | 15.8 | 49.5 | 6.2 | 21.2 | 59.4 | 102.9 | 125.4 |
| 1996 | 139.0 | 276.0 | 201.5 | 118.1 | 78.0 | 38.9 | 18.8 | 0.0 | 15.0 | 87.9 | 286.3 | 281.3 |
| 1997 | 179.5 | 210.0 | 80.0 | 100.0 | 78.0 | 33.5 | 8.0 | 0.0 | 0.0 | 13.3 | 287.0 | 234.0 |
| 1998 | 101.6 | 252.2 | 369.4 | 115.4 | 49.3 | 34.3 | 53.1 | -- | 25.0 | 5.5 | 28.4 | 106.4 |
| 1999 | 153.2 | 193.6 | 70.1 | 75.4 | 48.5 | 18.5 | 46.0 | 44.3 | 0.0 | 28.6 | 23.4 | 93.2 |
| 2000 | 153.2 | 193.6 | 70.1 | 75.4 | 48.5 | 18.5 | 46.0 | 44.3 | 0.0 | 28.6 | 23.4 | 93.2 |
| 2001 | 199.5 | 94.5 | 176.6 | 170.5 | 84.0 | 180.0 | 38.5 | 10.0 | 21.1 | 33.0 | 95.5 | 252.0 |
| 2002 | 206.0 | 251.0 | 299.5 | 224.0 | 65.0 | 87.0 | 118.5 | 52.4 | 10.0 | 0.0 | 310.3 | 129.4 |
| 2003 | 253.5 | 220.1 | 281.0 | 276.4 | 86.4 | 66.1 | 85.5 | 5.2 | 0.0 | 70.7 | 90.3 | 327.9 |
| 2004 | 178.5 | 467.7 | 489.0 | 121.6 | 41.8 | 99.9 | 79.2 | 28.4 | 25.8 | 35.8 | 149.7 | 514.3 |
| 2005 | 172.3 | 75.5 | 134.3 | 31.3 | 58.9 | 190.9 | 46.8 | 9.8 | 2.8 | 0.0 | 189.5 | -- |
| 2006 | 96.7 | 67.3 | -- | 25.1 | 28.4 | 170.6 | 11.5 | 8.0 | 0.0 | 55.0 | 47.9 | 111.1 |
| 2007 | 493.7 | 201.9 | 334.8 | 94.2 | 27.7 | 38.9 | 60.0 | 47.6 | 2.3 | 67.9 | 18.2 | 125.6 |
| 2008 | 99.7 | 237.2 | 57.6 | 25.9 | 6.6 | 22.7 | 42.4 | 14.3 | 0.0 | 7.2 | 0.0 | 28.1 |
| 2009 | 136.4 | 67.8 | 50.6 | 43.4 | 36.5 | 25.7 | 28.3 | 0.0 | 3.0 | 7.1 | 79.0 | -- |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Morrumbala

Elemento: Precipitação total mensal (das 9 às 9h, em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|------|------|------|------|------|------|------|-------|
| 1995 | 60.6 | 24.6 | 19.0 | 21.5 | 30.6 | 12.8 | 0.0 | 7.6 | 3.7 | 26.4 | 43.1 | 45.2 |
| 1996 | 61.2 | 32.3 | 39.3 | 74.1 | 25.5 | 24.3 | 8.9 | 5.6 | 2.3 | 22.9 | 25.8 | 73.5 |
| 1997 | 27.7 | 130.6 | 28.8 | 52.4 | 20.4 | 10.8 | 24.4 | 10.0 | 23.6 | 9.4 | 57.8 | 58.7 |
| 1998 | 40.6 | 97.6 | 21.7 | 32.3 | 8.6 | 14.6 | 9.4 | 4.8 | 0.5 | 70.6 | 60.8 | 20.8 |
| 1999 | 27.8 | 65.8 | 30.8 | 28.6 | 4.6 | 16.6 | 6.8 | 9.8 | 0.0 | 28.6 | 51.3 | 101.7 |
| 2000 | 167.5 | 270.5 | 129.7 | 69.9 | 20.5 | 8.6 | 20.8 | 10.8 | 2.3 | 1.2 | 42.2 | 48.0 |
| 2001 | 68.4 | 60.2 | 111.7 | 28.8 | 32.5 | 14.2 | 8.6 | -- | 0.0 | 4.6 | 15.6 | 58.4 |
| 2002 | 100.6 | 70.2 | 48.2 | 12.8 | 0.0 | 12.2 | 22.4 | 24.8 | 4.7 | 50.3 | 38.2 | 48.8 |
| 2003 | 70.2 | 78.6 | 98.8 | 22.4 | 11.2 | 34.2 | 28.2 | 8.4 | 56.2 | 12.0 | 78.2 | 40.6 |
| 2004 | 60.3 | 69.8 | 50.5 | 4.0 | 10.8 | 26.8 | 37.1 | 4.5 | 0.8 | 29.5 | 66.5 | 386.4 |
| 2005 | 132.7 | 133.6 | 188.2 | 32.4 | 0.0 | 7.0 | 37.0 | 0.0 | 9.2 | 27.0 | 63.6 | 129.7 |
| 2006 | 166.4 | 157.1 | 188.9 | 75.3 | 25.8 | 19.9 | 42.3 | 42.5 | 36.0 | 47.2 | 83.7 | 199.9 |
| 2007 | 622.6 | 65.6 | 420.5 | 38.9 | 9.2 | 0.0 | 36.6 | 30.4 | 3.6 | 22.5 | 71.0 | 263.9 |
| 2008 | 191.1 | 487.9 | 151.7 | 59.5 | 27.8 | 27.2 | 20.2 | 0.9 | -- | 41.6 | 90.5 | 118.8 |
| 2009 | 306.3 | 132.8 | 71.4 | 37.1 | 38.1 | 3.8 | 53.4 | 58.3 | 6.9 | 0.0 | 25.9 | 268.8 |
| 2010 | 175.7 | 245.4 | 101.5 | 132.3 | 29.8 | 30.2 | 47.8 | 9.7 | 45.1 | 91.9 | 38.9 | 372.7 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Angoche

Elemento: Precipitação total mensal (das 9 às 9h, em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|------|-------|------|------|------|------|-------|-------|
| 1996 | 194.7 | 245.0 | 639.7 | 34.3 | 16.1 | 79.6 | 14.5 | 14.3 | 0.4 | 17.9 | 2.4 | 237.9 |
| 1997 | 258.0 | 317.3 | 122.7 | 172.8 | 59.3 | 9.2 | 26.8 | 4.9 | 1.5 | 12.5 | 12.3 | 364.8 |
| 1998 | 221.2 | 248.6 | 120.3 | 52.4 | 1.8 | 5.4 | 54.4 | 36.1 | 0.2 | 0.1 | 2.4 | 20.7 |
| 1999 | 160.4 | 145.1 | 94.0 | 175.1 | 10.5 | 29.6 | 35.2 | 15.6 | 9.2 | 0.7 | 8.2 | 105.8 |
| 2000 | 270.9 | 351.5 | 28.4 | 122.3 | 24.6 | 21.5 | 3.3 | 45.3 | 22.6 | 4.6 | 153.4 | 316.8 |
| 2001 | 227.6 | 137.4 | 261.8 | 110.1 | 16.7 | 11.3 | 20.0 | 12.7 | 0.7 | 14.1 | 32.0 | 104.1 |
| 2002 | 228.9 | 168.7 | 296.5 | 110.1 | 33.0 | 97.7 | 52.3 | 32.9 | 11.4 | 2.8 | 10.9 | 188.1 |
| 2003 | 394.8 | 170.1 | 132.4 | 21.2 | 0.5 | 36.6 | 30.3 | 2.4 | 0.3 | 0.0 | 15.8 | 69.9 |
| 2004 | 327.9 | 217.0 | 215.1 | 216.6 | 16.0 | 47.0 | 24.6 | 9.4 | 0.2 | 3.4 | 23.6 | 67.4 |
| 2005 | 302.8 | 63.8 | 4.6 | 70.2 | 21.9 | 68.6 | 47.4 | 0.0 | 2.7 | 48.3 | 3.6 | 84.2 |
| 2006 | 65.3 | 104.5 | 100.2 | 179.2 | 1.1 | 27.7 | 17.4 | 0.8 | 0.9 | 0.2 | 37.1 | 79.3 |
| 2007 | 310.2 | 189.8 | 90.8 | 194.9 | 79.4 | 21.1 | 18.3 | 5.1 | 0.7 | 37.7 | 1.3 | 108.3 |
| 2008 | 89.2 | 234.1 | 59.4 | 16.7 | 19.9 | 27.3 | 8.7 | 18.5 | 41.1 | 0.5 | 11.2 | 51 |
| 2009 | 149.2 | 375.6 | 291.7 | 159.9 | 47.4 | 41.9 | 52.2 | 19.0 | 57.4 | 2.1 | 83.0 | 73.2 |
| 2010 | 235.6 | 194.0 | 120.3 | 26.0 | 25.5 | 75.0 | 44.7 | 33.1 | 0.0 | 7.4 | -- | 54.8 |
| 2011 | 348.9 | 147.1 | 81.7 | 38.3 | 73.6 | 115.8 | -- | 40.6 | 0.0 | 2.9 | 97.4 | 51.3 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Nametil

Elemento: Precipitação total mensal (das 9 as 9 horas, em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|------|------|------|------|------|-------|-------|-------|
| 1991 | 375.4 | 236.6 | 321.7 | 79.2 | 18.8 | 26.1 | 20.3 | 3.8 | 0.7 | 47.1 | 173.2 | 161.5 |
| 1992 | 178.6 | 278.9 | 71.8 | 122.4 | 21.9 | 13.3 | 6.5 | 8.1 | 38.3 | 123.7 | 86.2 | 229.2 |
| 1993 | 274.3 | 34.4 | 51.6 | 98.9 | 13.5 | 19.2 | 30.4 | 3.7 | 0.3 | 16.9 | 73.2 | 246.2 |
| 1994 | 165.6 | 365.7 | 236.7 | 38.1 | 53.1 | 74.6 | 47.8 | 4.7 | 10.4 | 3.2 | 59.3 | 174.1 |
| 1995 | 245.4 | 215.2 | 61.5 | 129.7 | 5.7 | 27.7 | 3.3 | 6.4 | 0.0 | 59.7 | 30.8 | 257.7 |
| 1996 | 70.1 | 226.3 | 185.8 | 164.2 | 19.4 | 43.4 | 2.6 | 9.3 | 3.1 | 35.2 | 15.3 | 230.9 |
| 1997 | 276.2 | 63.3 | 62.5 | 46.3 | 7.6 | 4.7 | 11.8 | 6.5 | 32.4 | 38.5 | 96.1 | 145.1 |
| 1998 | 117.7 | 265.3 | 189.5 | 157.7 | 1.7 | 20.9 | 9.1 | 0.0 | 4.7 | 34.4 | 56.2 | 374.9 |
| 1999 | 70.4 | 241.0 | 166.7 | 123.7 | 10.5 | 32.9 | 32.9 | 2.7 | 5.0 | 0.0 | 122.7 | 148.7 |
| 2000 | 103.6 | 101.2 | 215.8 | 124.6 | 12.2 | 19.2 | 12.9 | 23.0 | 1.0 | 13.0 | 12.2 | 239.0 |
| 2001 | 50.8 | 198.5 | 119.1 | 85.0 | 9.6 | 31.9 | 28.0 | 0.3 | 3.5 | 66.0 | 22.1 | 228.1 |
| 2002 | 353.4 | 201.3 | 154.3 | 77.3 | 13.3 | 6.0 | 31.2 | 23.5 | 2.7 | 42.1 | 128.0 | 156.7 |
| 2003 | 313.9 | 165.0 | 102.3 | 59.5 | 13.1 | 11.1 | 30.0 | 17.4 | 3.0 | 0.4 | 0.0 | 117.7 |
| 2004 | 206.8 | 301.4 | 216.8 | 63.5 | 23.0 | 8.9 | 20.8 | 8.3 | 0.0 | 0.0 | 160.5 | 271.6 |
| 2005 | 200.8 | 143.4 | 192.7 | 369.5 | 12.4 | -- | 23.8 | 29.6 | 69.0 | 130.6 | 97.4 | 279.5 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Lichinga

Elemento: Precipitação total mensal (das 9 as 9 horas em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|-------|------|------|-----|-------|------|-------|-------|
| 1995 | 246.4 | 223.9 | -- | 28.9 | 23.0 | 0.0 | 0.7 | 0.0 | 0.0 | 0.0 | 12.4 | -- |
| 1996 | 221.8 | 220.0 | 257.6 | 86.6 | 67.6 | 1.1 | 0.2 | 0.0 | 188.4 | 5.2 | 0.7 | 146.6 |
| 1997 | 224.2 | 129.3 | 65.1 | 166.2 | 106.2 | 0.0 | 1.9 | 0.0 | 0.0 | 67.8 | 112.4 | 399.8 |
| 1998 | 286.5 | 61.5 | 156.5 | 71.9 | 4.8 | 0.0 | 0.0 | 0.0 | 0.0 | 81.4 | 9.5 | 70.1 |
| 1999 | 370.6 | 291.4 | 558.0 | 94.5 | 30.9 | 15.3 | 0.5 | 6.6 | 0.2 | 6.2 | 110.1 | 94.4 |
| 2000 | 375.2 | 201.3 | 245.7 | 32.8 | 0.0 | 1.7 | 3.7 | 0.0 | 0.0 | 13.4 | 219.7 | 219.6 |
| 2001 | 183.0 | 247.2 | 359.8 | 39.9 | 12.5 | 0.0 | 0.0 | 1.4 | 0.0 | 24.7 | 5.2 | 217.5 |
| 2002 | 550.1 | 371.2 | 153.3 | 73.4 | 2.0 | 3.8 | 0.0 | 0.5 | 2.8 | 1.4 | 64.4 | 215.3 |
| 2003 | 402.2 | 266.8 | 351.3 | 30.6 | 0.0 | 0.0 | 4.5 | 1.3 | 0.0 | 0.0 | 113.4 | 249.3 |
| 2004 | 254.6 | 175.8 | 124.2 | 126.1 | 7.0 | 3.8 | 2.1 | 1.9 | 1.4 | 36.1 | 74.8 | 328.5 |
| 2005 | 269.9 | 123.6 | 160.5 | 93.4 | 70.1 | 11.7 | 7.9 | 1.5 | 11.9 | 7.6 | 12.4 | 327.7 |
| 2006 | 257.4 | 221.7 | 318.2 | 49.1 | 15.8 | 0.2 | 0.4 | 0.2 | 0.0 | 33.3 | 279.7 | 101.1 |
| 2007 | 129.3 | 155.5 | 111.3 | 17.8 | 6.0 | 0.8 | 3.3 | 0.0 | 0.0 | 53.0 | 9.5 | 355.9 |
| 2008 | 425.2 | 195.5 | 97.2 | 31.4 | 28.1 | 5.3 | 0.2 | 8.2 | 0.0 | 32.1 | 166.0 | 279.5 |
| 2009 | 363.8 | 323.0 | 192.3 | 70.3 | 2.7 | 0.2 | 1.6 | 0.1 | 0.0 | 24.9 | 122.5 | 218.5 |
| 2010 | 162.3 | 241.2 | 263.8 | 126.2 | 20.0 | 8.0 | 22.8 | 6.2 | 0.3 | 1.0 | 11.8 | 37.8 |
| 2011 | 192.3 | 65.8 | 275.1 | 34.5 | 2.6 | 0.0 | 0.0 | 0.0 | 0.0 | 17.0 | 62.0 | 108.2 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Inception Report

Estação: Mocimboa da Praia

Elemento: Precipitação total mensal (das 9 as 9 horas em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|--------|-------|-------|-------|------|------|------|------|-------|-------|-------|
| 1996 | 186.9 | 251.7 | 109.9 | 39.7 | 249.5 | 10.3 | 10.4 | -- | 0.0 | 55.5 | 1.1 | 20.8 |
| 1997 | 75.6 | 150.9 | -- | 140.9 | 60.6 | 96.9 | 33.6 | 5.3 | 0.0 | 34.6 | 73.4 | 276.2 |
| 1998 | 470.6 | 207.9 | 122.8 | 255.4 | 42.0 | 13.9 | 0.3 | 16.4 | 19.5 | 8.4 | 6.8 | 35.5 |
| 1999 | 147.6 | 194.8 | 187.1 | 186.1 | 48.2 | 29.0 | 72.8 | 45.0 | -- | -- | 36.0 | 185.8 |
| 2000 | 26.3 | 140.7 | 344.2 | 31.2 | 43.3 | 72.5 | 54.4 | 27.1 | -- | 10.7 | 135.3 | 205.7 |
| 2001 | 185.9 | 144.4 | 162.0 | 185.9 | 30.5 | 6.0 | 0.0 | 0.0 | 0.0 | 24.5 | 0.0 | 138.0 |
| 2002 | 145.4 | 72.8 | 174.8 | 236.5 | 11.9 | 0.0 | 3.4 | 9.1 | 38.3 | 2.3 | 60.9 | 118.6 |
| 2003 | 165.2 | 210.3 | 301.5 | 70.3 | 10.6 | 4.5 | 8.0 | 11.0 | 0.0 | 0.0 | 0.0 | 171.9 |
| 2004 | 234.5 | 396.2 | 115.4 | 269.1 | 21.9 | -- | 0.0 | 2.1 | 2.0 | 16.3 | 76.0 | 300.9 |
| 2005 | 109.9 | -- | 110.4 | 76.6 | 95.8 | 13.9 | 3.6 | 28.8 | 5.4 | 7.2 | 3.0 | 13.7 |
| 2006 | 122.9 | 175.1 | 263.3 | 158.6 | 129.5 | 9.8 | 19.3 | 23.1 | 7.6 | 3.4 | 58.9 | 130.9 |
| 2007 | 83.5 | 22.5 | 119.6 | 146.4 | 8.4 | 8.6 | 10.8 | 25.5 | 48.8 | 50.9 | 8.6 | 66.5 |
| 2008 | 129.9 | 154.7 | 140.9 | 176.4 | 5.6 | 13.9 | 5.3 | 0.0 | 11.2 | 169.4 | 42.1 | 91.1 |
| 2009 | 75.0 | 2158.5 | 161.5 | 139.2 | 46.8 | 6.0 | 18.3 | 1.3 | 5.7 | 11.7 | 4.7 | 123.1 |
| 2010 | 181.5 | 117.9 | 292.5 | 227.4 | 18.5 | 14.4 | 19.7 | 20.4 | 0.0 | 0.0 | 11.8 | 83.1 |
| 2011 | 185.9 | 144.4 | 173.6 | 72.6 | 7.5 | 10.3 | 10.4 | 14.1 | 7.8 | 49.2 | 3.2 | 153.9 |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Estação: Mueda

Elemento: Precipitação total mensal (das 9 as 9 horas em mm)

| ANO | JAN | FEV | MAR | ABR | MAI | JUN | JUL | AGO | SET | OUT | NOV | DEZ |
|------|-------|-------|-------|-------|-------|------|------|------|------|------|-------|-------|
| 1997 | 116.3 | 160.6 | 146.0 | 52.3 | 18.6 | 9.8 | 0.2 | 1.8 | 4.4 | 10.0 | 70.5 | 136.0 |
| 1998 | 209.3 | 281.5 | 369.0 | 185.3 | 46.9 | 8.8 | 38.6 | 5.9 | 4.9 | 10.7 | 128.4 | 363.6 |
| 1999 | 64.8 | 260.2 | 225.7 | 176.9 | 11.4 | 13.2 | 0.4 | 2.6 | 0.3 | 15.6 | 26.1 | 44.9 |
| 2000 | 355.9 | 208.2 | 196.9 | 149.3 | 7.6 | 2.6 | 8.3 | 14.8 | 0.4 | 7.9 | 48.4 | 216.7 |
| 2001 | 179.0 | 329.3 | 118.4 | 214.2 | 10.2 | 12.0 | 16.2 | 0.0 | 3.5 | 1.2 | 0.2 | 176.8 |
| 2002 | 201.2 | 172.7 | 96.6 | 175.1 | 34.4 | 38.8 | 1.7 | 0.0 | 0.3 | 1.6 | 165.0 | 84.3 |
| 2003 | 136.7 | 157.4 | 187.4 | 220.0 | 33.3 | 4.5 | 1.7 | 0.2 | 3.2 | 0.3 | 53.6 | 201.9 |
| 2004 | 81.5 | 150.2 | 229.3 | 115.3 | 12.5 | 0.2 | 0.3 | 0.0 | 1.9 | 6.4 | 30.8 | -- |
| 2005 | 77.9 | 108.5 | 52.0 | 38.2 | 7.3 | 2.5 | 0.0 | 5.0 | 4.2 | 0.0 | 17.6 | 111.2 |
| 2006 | 96.2 | 100.7 | 374.5 | 53.1 | 15.8 | 0.0 | 0.0 | 3.4 | 0.0 | 0.0 | 1.1 | 232.0 |
| 2007 | 406.0 | 137.5 | 95.3 | 94.6 | 0.0 | 0.0 | 0.0 | 0.0 | 20.3 | 4.9 | 11.4 | 205.8 |
| 2008 | 255.7 | 445.7 | 146.3 | 56.3 | 2.9 | 4.2 | 0.5 | 0.0 | 0.0 | 5.3 | 35.1 | 100.1 |
| 2009 | 88.2 | 156.4 | 165.9 | 95.6 | 31.5 | 0.5 | 0.9 | 13.9 | 0.2 | 4.1 | 149.2 | 194.0 |
| 2010 | 141.3 | 510.1 | 159.5 | 291.0 | 77.7 | 5.5 | 0.0 | 7.5 | 4.1 | 0.0 | 35.3 | 111.1 |
| 2011 | 101.5 | 373.8 | 302.6 | 203.3 | 111.4 | 19.1 | 0.0 | 0.0 | 6.0 | -- | -- | -- |
| -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- | -- |

Appendix D – Map of Study Roads

